

A PORTION OF SECTION 33, TOWNSHIP 31 NORTH, RANGE 5 EAST, W.M.

LEGEND

---	PROJECT BOUNDARY
---	R/W LINE, EXIST
---	UTILITY EASEMENT
---	EXIST. PARCEL LINE
---	BUILDING SETBACK
---	SEWER MAIN, EXIST
---	STORM LINE, EXIST
---	PROPOSED STORM CULVERT
---	WATER LINE, EXIST
---	POWER LINE, EXIST
---	GAS LINE, EXIST
---	PROPOSED PAVED AREA
---	SEWER MANHOLE, EXIST
---	STORM CATCH BASIN, EXIST
---	FIRE HYDRANT, EXIST
---	POWER POLE, EXIST
---	BUS STOP SIGN, EXIST

DEVELOPMENT STANDARDS

Zoning	GC
Minimum Street Setback	None
Minimum Interior Setback	None
Maximum Base Height	35'
Maximum Impervious Surface	85%

Landscape Setbacks:

Public Right-of-Way & Private Access	15'
Public Arterial Right-of-Way	15'

LANDSCAPE DATA

Total Site Area	129,163 sf (2.97 ac)
Landscaping Required	19,348 sf (15% of Total Area)
Landscaping Provided	27,278 sf

LAND DISTURBING AREA

Total Site Area	129,163 sf (2.97 ac)
Impervious Area	74,812 sf
Parking	3,016 sf
Sidewalk	930 sf
Decorative Walk	196 sf
Trash/Recycle Area	78,954 sf
PGIS Total	
Roof	22,931 sf (78.8%)
Total Impervious	101,885 sf (78.8%)

Land Disturbing Activity

Conceptual Area of Disturbance	129,163 sf (2.97 ac)
--------------------------------	----------------------

Site Grading

Cut	-cy
Fill	3,000 cy

PARKING CALCULATIONS

Commercial Use Building (Floor Area)	21,858 sf
Motor Vehicle Sales and Service Land Use	6
Service Bays (1 space/1-Service Bay)	12 Spaces
Outdoor Display Area (1 space/1,000sf)	23,126sf
Office Space (1 space/400sf)	24 Spaces
Parking Required	3,000 sf
Parking Provided	44 Spaces
ADA Spaces Provided	233 Spaces
ADA Spaces Provided	2 Spaces

BUILDING DESIGNATIONS (Interior Area)


Building	Office	3,000 sf*
	Sales & Service Support	21,858 sf*
	Total	24,858 sf*

*Note: Areas tabulated are for the interior portion of the buildings consistent with architectural plans. Building Footprint Areas are represented on site plan for stormwater management calculations.

Note: Per MMC 22G.020.340(2) any mechanical equipment located on roof or external portions of a building shall be architecturally screened.

BICYCLE PARKING CALCULATIONS

Bicycle Parking (5% of Vehicle Spaces)	5% of 44 Spaces
Bicycle Parking Provided	2.2 Bicycle Stalls
Bicycle Parking Provided	3 Bicycle Stalls



VICINITY MAP

LEGAL DESCRIPTION

PARCEL A: LOT 4 OF SHORT PLAT NO. SP-10215-82) RECORDED UNDER RECORDING NO. 821129093, RECORDS OF SNOHOMISH COUNTY, WASHINGTON, BEING A PORTION OF NORTHWEST QUARTER OF THE NORTHWEST QUARTER OF SECTION 33, TOWNSHIP 31 NORTH, RANGE 5 EAST, W.M., SNOHOMISH COUNTY, WASHINGTON.

EXCEPT THAT PORTION CONVEYED TO SNOHOMISH COUNTY BY DEED RECORDED UNDER RECORDING NO. 9412080055.

PARCEL B: PARCEL B OF CITY OF MARYSVILLE BOUNDARY LINE ADJUSTMENT NO. BLA20-008, RECORDED UNDER SNOHOMISH COUNTY AUDITOR'S FILE NO. 2021-3255002.

DATUM & BENCHMARK

DATUM: HORIZONTAL DATUM: NAD 83/2011 VERTICAL DATUM: NAVD 88

GENERAL NOTES

- PRECISION OF CONTROL TRAVERSE IS AT HIGHER LEVEL THAN MINIMUM STANDARDS REQUIRED BY WAC 332-130-090.
- FIELD SURVEY CONDUCTED USING A COMBINATION OF GPS USING THE WASHINGTON STATE REFERENCE NETWORK (WSRN) AND/OR A 5 SECOND DIRECT READING TOTAL STATION. METHOD: GPS, TRAVERSE AND RADIAL SURVEY.
- ALL DISTANCES ARE IN FEET.
- THIS SURVEY REPRESENTS VISIBLE PHYSICAL IMPROVEMENT CONDITIONS EXISTING ON MARCH 4, 2020. ALL SURVEY CONTROL INDICATED AS "FOUND" WAS RECOVERED FOR THIS PROJECT IN MARCH OF 2020.

SUBSTRUCTURES

BURIED UTILITIES ARE SHOWN AS INDICATED ON RECORDS MAPS FURNISHED BY OTHERS AND VERIFIED WHERE POSSIBLE BY FEATURES LOCATED IN THE FIELD. WE ASSUME NO LIABILITY FOR THE ACCURACY OF THOSE RECORDS. FOR THE FINAL LOCATION OF EXISTING UTILITIES CRITICAL TO DESIGN, CONTACT THE UTILITY OWNER/AGENCY.

TELECOMMUNICATIONS/FIBER OPTIC DISCLAIMER

RECORDS OF UNDERGROUND TELECOMMUNICATIONS AND/OR FIBER LINES ARE NOT ALWAYS AVAILABLE TO THE PUBLIC. NORTH PEAK ASSOCIATES LLC HAS NOT CONTACTED EACH OF THE MANY COMPANIES IN THE COURSE OF THIS SURVEY WHICH MAY HAVE UNDERGROUND LINES WITHIN THE ADJACENT RIGHTS-OF-WAY. NORTH PEAK ASSOCIATES LLC DOES NOT ACCEPT RESPONSIBILITY FOR THE EXISTENCE OF UNDERGROUND TELECOMMUNICATIONS/FIBER OPTIC LINES WHICH ARE NOT MADE PUBLIC RECORD WITH THE LOCAL JURISDICTION.

PROJECT INFORMATION

Total Parcel Numbers	310533-002-052-00 & 310533-002-053-00
Total Area	129,163.97
GPP Designation	GC (General Commercial)
Existing Zoning	Undeveloped
Existing Land Use	General Commercial
Proposed Land Use	General Commercial

LOCAL SERVICES

Sewage Disposal:	City Of Marysville
Water District:	City Of Marysville
School District:	Marysville #25
Fire District:	City Of Marysville
Post Office:	City Of Marysville
Electric:	Snohomish County PUD
Phone:	Frontier
Cable:	Comcast
Gas:	PSE

CONTACT PERSON

Land Technologies Inc.
Merle Ash
18820 3rd Ave. NE
Arlington, WA 98223
360.652.9727
merle@landtechway.com

ENGINEER

Land Technologies, Inc.
Tyler S. Foster, P.E.
18820 3rd Ave NE
Arlington, WA 98223
360.652.9727
tyler@landtechway.com

SURVEYOR

North Peak Associates LLC
Steven C. Berg, PLS
17270 Woodville-Redmond Rd
Woodinville, WA 98072
206.601.4682

SITE ADDRESS


15223 Smokey Point Blvd
Marysville, WA 98271

APPLICANT/OWNER

Quality Auto Center
15223 Smokey Point Blvd
Marysville, WA 98271

CERTIFIED EROSION CONTROL SPECIALIST

Quality Auto Center
15223 Smokey Point Blvd
Marysville, WA 98271





PRELIMINARY SITE PLAN

SIGNS

All signs are to comply with MMC 22C.160.160(1)

NOTES

- Where illuminated signs and illuminated areas are permitted, such illuminating devices shall be shielded and/or directed so as not to visibly create a nuisance to any property in a residential zone classification. Residential zoning is located to the east of the proposed development.
- Mechanical equipment located on the roof, facade or external portions of a building shall be architecturally screened so as not to be visible from adjacent properties at street level or the public street.
- Equipment or vents which generate noise or air emissions shall be located on the opposite side of the building from adjoining residentially designated properties.
- Industrial and exterior lighting shall not be used in such a manner that it produces glare on public highways. Arc welding, acetylene-torch cutting, or similar processes shall be performed so as not to be seen from any point beyond the outside of the property.
- The storage and handling of inflammable liquids, liquefied petroleum gases, and explosives shall comply with rules and regulations falling under the jurisdiction of the city's fire chief, and the laws of the state of Washington. Bulk storage of inflammable liquids below ground shall be permitted, and the tanks shall be located not closer to the property line than the greatest dimension (diameter, length or height) of the tank.
- Provisions shall be made for necessary shielding or other preventive measures against interference as occasioned by mechanical, electrical and nuclear equipment, and uses or processes with electrical apparatus in nearby buildings or land uses.
- Liquid and solid wastes and storage of animal or vegetable waste which attract insects or rodents or otherwise create a health hazard shall be prohibited. No waste products shall be exposed to view from eye level from any property line in an industrial district.
- All necessary power lines, telephones wires, television cables, fire alarm systems and other communication wires, cables or lines shall be placed in underground location either by direct burial or by means of conduit or duct. All such underground installations or systems shall be approved by the appropriate utility company and shall adhere to all governing applicable regulations including, but not limited to, the applicable City and State regulations and specific requirements of the appropriate utility pursuant to MMC Section 22G.120.270.



Sheet List Table

Sheet Number	Sheet Title
Planning: P2	
P1	Preliminary Site Plan
P2	Survey Existing Conditions
Construction: C10	
C1	Civil Site Plan
C2	Construction Notes
C3	Existing Conditions, Clearing & TESC Plan
C4	Grading Plan
C5	Grading & TESC Details
C6	Site Cross Sections
C7	Site Cross Sections
C8	Paving Plan
C9	Stormwater Management Overview Plan
C10	Stormwater Management Details

QUALITY AUTO CENTER

15223 Smokey Point Blvd, Marysville, WA 98271

AQUIFER RECHARGE/ WELL HEAD PROTECTION

Low, Over 100

SOILS

Custer Fine Sandy Loam;
Hydrologic Soil Group: C/D
Compact Fill Area to 95%
Modified Proctor

CALL AT LEAST
2 BUSINESS
DAYS BEFORE
YOU DIG
1-800-424-5555

LAND TECHNOLOGIES
18820 Third Avenue, N.E.
Arlington, WA 98223
360-652-9727

PROJECT LEAD: Merle Ash
CHECKED BY: Tyler Foster
DRAWN BY: Merle Ash
DATE: 11/15/2022
REVISION 1: -
REVISION 2: -
REVISION 3: -
REVISION 4: -
AS-BUILT: -

Quality Auto Center Marysville
15223 Smokey Point Blvd, Marysville, WA 98271
A PORTION OF SECTION 33, TOWNSHIP 31 NORTH, RANGE 5 EAST, W.M.

Quality Auto Center
15223 Smokey Point Blvd, Marysville, WA 98271

SHEET
P1 of P2
24x36
PA 22-

NW 1/4 OF THE NW 1/4, SEC. 33, TWP. 31 N., RGE. 5 E., W.M.

SITE NOTES
 ADDRESS:
 15223 SMOKEY POINT BLVD
 MARYSVILLE, WA 98271
 PARCEL NO.:
 31053300205200 & 31053300205300
FLOOD ZONE:
 THIS SITE APPEARS ON NATIONAL FLOOD INSURANCE RATE MAP,
 DATED NOVEMBER 8, 1999, COMMUNITY PANEL NO. 53061C0395E,
 AND IS SITUATED IN ZONE "X", AREA DETERMINED TO BE OUTSIDE
 OF THE 500-YEAR FLOODPLAIN.

ZONING AGENCY:
 MARYSVILLE CITY HALL
 1049 STATE AVENUE
 MARYSVILLE, WA 98270

ZONING:
 GC GENERAL COMMERCIAL

HORIZONTAL DATUM:
 NAD 83/2011

VERTICAL DATUM:
 NAVD 88

AREA:
 SITE AREA AS SHOWN CONTAINS 129,163 SQUARE FEET OR 2.9652
 ACRES, MORE OR LESS.

SUBSTRUCTURES:
 BURIED UTILITIES ARE SHOWN AS INDICATED ON RECORDS MAPS
 FURNISHED BY OTHERS AND VERIFIED WHERE POSSIBLE BY
 FEATURES LOCATED IN THE FIELD. WE ASSUME NO LIABILITY FOR
 THE ACCURACY OF THOSE RECORDS. FOR THE FINAL LOCATION OF
 EXISTING UTILITIES CRITICAL TO DESIGN, CONTACT THE UTILITY
 OWNER/AGENCY.

TELECOMMUNICATIONS/FIBER OPTIC DISCLAIMER:
 RECORDS OF UNDERGROUND TELECOMMUNICATIONS AND/OR FIBER
 LINES ARE NOT ALWAYS AVAILABLE TO THE PUBLIC. NORTH PEAK
 ASSOCIATES LLC HAS NOT CONTACTED EACH OF THE MANY
 COMPANIES IN THE COURSE OF THIS SURVEY WHICH MAY HAVE
 UNDERGROUND LINES WITHIN THE ADJACENT RIGHTS-OF-WAY.
 NORTH PEAK ASSOCIATES LLC, DOES NOT ACCEPT RESPONSIBILITY
 FOR THE EXISTENCE OF UNDERGROUND TELECOMMUNICATIONS/FIBER
 OPTIC LINES WHICH ARE NOT MADE PUBLIC RECORD WITH THE
 LOCAL JURISDICTION.

LEGAL DESCRIPTION:



PARCEL A:
 LOT 4 OF SHORT PLAT NO. SP-102(5-82) RECORDED UNDER
 RECORDING NO. 8211290093, RECORDS OF SNOHOMISH COUNTY,
 WASHINGTON, BEING A PORTION OF NORTHWEST QUARTER OF THE
 NORTHWEST QUARTER OF SECTION 33, TOWNSHIP 31 NORTH, RANGE
 5 EAST, W.M., SNOHOMISH COUNTY, WASHINGTON.

EXCEPT THAT PORTION CONVEYED TO SNOHOMISH COUNTY BY DEED
 RECORDED UNDER RECORDING NO. 9412080055.


PARCEL B:
 PARCEL B OF CITY OF MARYSVILLE BOUNDARY LINE ADJUSTMENT
 NO. BLA20-008, RECORDED UNDER SNOHOMISH COUNTY AUDITOR'S
 FILE NO. 202103255002.

GENERAL NOTES:

- PRECISION OF CONTROL TRAVERSE IS AT HIGHER LEVEL THAN
 MINIMUM STANDARDS REQUIRED BY WAC 332-130-090.
- FIELD SURVEY CONDUCTED USING A COMBINATION OF GPS USING
 THE WASHINGTON STATE REFERENCE NETWORK (WSRN) AND/OR
 A 5 SECOND DIRECT READING TOTAL STATION. METHOD: GPS,
 TRAVERSE AND RADIAL SURVEY.
- ALL DISTANCES ARE IN FEET.
- THIS SURVEY REPRESENTS VISIBLE PHYSICAL IMPROVEMENT
 CONDITIONS EXISTING ON MARCH 4, 2020. ALL SURVEY CONTROL
 INDICATED AS "FOUND" WAS RECOVERED FOR THIS PROJECT IN
 MARCH OF 2020.




SECTION BREAKDOWN
 1" = 1500'



LEGEND

SS	SANITARY SEWER	OHP/OHT	OVERHEAD POWER/TELEPHONE
CIP	IRON PIPE	SD	STORM DRAIN
EM	ELECTRICAL METER	W	WATER MAIN
⊙	FIRE HYDRANT	⊕	WATER MANHOLE
⊙	FOUND NAIL	WM	WATER METER
⊙	FOUND MONUMENT IN CASE	⊕	WATER VALVE
●	FOUND REBAR	WF	WOOD FENCE
G	GAS MAIN	CED	CEDAR TREE
GM	GAS METER	FIR	FIR TREE
⊕	GAS VALVE	MAP	MAPLE TREE
⊕	MANHOLE		



DATE	03/17/20	SCALE	1" = 30'	DRAWN BY	ES	CHECKED BY	SB	NO.	
NORTH PEAK ASSOCIATES LLC PROFESSIONAL LAND SURVEYORS 17270 WOODINVILLE REDMOND ROAD NE, SUITE 705 WOODINVILLE, WA 98072 (206) 607-4682 WWW.NORTHPEAKASSOCIATES.COM									
BOUNDARY AND TOPOGRAPHIC SURVEY QUALITY AUTO CENTER					WASHINGTON SNOHOMISH MARYSVILLE				
JOB NO. 20-12									
SHEET P2 OF P2									