



MARYSVILLE
PUBLIC WORKS

TO: Rochelle Smith, Land Pro Group, Inc.
FROM: Ryan Keefe, Water Operations Lead II
DATE: October 26th, 2022
SUBJECT: Fire Flow Test for 87th Ave & 40th St PRD

Water Operations performed a fire flow test on October 26th, 2022 for 87th Ave & 40th St PRD. The results were as follows:

Static: 75 psi
Residual: 71 psi
Pitot: 52 psi
GPM: 1216
GPM @ 20 psi: 5007

The test was performed using Hose Monster equipment with the GPM taken from their flow chart. The GPM @ 20 psi was determined using the hydrant flow test calculator located on the Hose Monster website.

Any questions please contact me at 360-363-8168 or rkeefe@marysvillewa.gov.

(360) 363-8100

Public Works
80 Columbia Avenue
Marysville, WA 98270