



JGM Site

**LFLC** FORM LIGHTING AND CONTROLS

#	Date	Comments	
<b>Revisions</b>			

Drawn By:
Checked By:
Date: 1/6/2023
Scale:

JGM Site                      Site Ltg. Calc.

Luminaire Schedule										
Symbol	Qty	Label	Arrangement	Tag	Description	Mounting Height	LLF	Luminaire Lumens	Luminaire Watts	BUG Rating
	5	W1	Single	LUMECON	LDS-LFC-160-BK-T4-1-30-WM	18	0.950	21242	160	B3-U0-G3
	2	B1	Single	CREE	PWY-EDG-5M-P4-02-E-UL-BK-525-30K	3.5	0.950	2404	34	B2-U0-G2
	1	A2-2	Back-Back	CREE	OSQM-B-16L-30K7-4M-UL-NM-BK OSQ-ML-B-DA-BK OSQ-BLSMF	25	0.950	11925	104	B1-U0-G2
	6	A2	Single	CREE	OSQM-B-16L-30K7-4M-UL-NM-BK OSQ-ML-B-DA-BK OSQ-BLSMF	25	0.950	11925	104	B1-U0-G2
	7	A1	Single	CREE	OSQX-B-40L-30K7-4M-UL-NM-BK OSQ-X-B-AA-BK OSQ-BLSXF	25	0.950	29300	301	B2-U0-G4

Calculation Summary							
Label	CalcType	Units	Avg	Max	Min	Avg/Min	Max/Min
Existing Parking Lot	Illuminance	Fc	2.68	9.9	0.2	13.40	49.50
Fence Line	Illuminance	Fc	0.17	1.3	0.0	N.A.	N.A.
General Storage	Illuminance	Fc	0.55	4.3	0.1	5.50	43.00
Overflow Parking	Illuminance	Fc	1.34	5.6	0.2	6.70	28.00
Temp Trailer Storage	Illuminance	Fc	1.16	6.2	0.2	5.80	31.00
Temp Truck & Vehicle Storage	Illuminance	Fc	1.02	6.0	0.1	10.20	60.00
Tool Storage	Illuminance	Fc	2.01	5.7	0.2	10.05	28.50