

CITY OF MARYSVILLE

EXECUTIVE SUMMARY FOR ACTION

CITY COUNCIL MEETING DATE: December 14, 2020

AGENDA ITEM: PA 20-___ – Public hearing on Ordinance No. 3168, establishing an interim regulation on “enhanced services facilities”	AGENDA SECTION: New Business	
PREPARED BY: Allan Giffen, Interim Community Development Director	APPROVED BY: <i>Allan Giffen</i> , CD Interim Director	
ATTACHMENTS: Ordinance No. 3168		
	MAYOR	CAO
BUDGET CODE: Not applicable	AMOUNT: Not applicable	

DESCRIPTION:

On November 23, 2020, the City Council adopted Ordinance 3168, establishing a six-month interim regulation prohibiting the siting of enhanced services facilities within the City of Marysville. Under RCW 36.70A.390 a city may adopt interim regulations, provided it holds a hearing on the interim regulation within 60 days of establishing the regulation. Ordinance No. 3168 established December 14, 2020, as the city council hearing date.

The Marysville Municipal Code (MMC) does not have a land use category for enhanced services facilities. The purpose of the interim regulation is to allow adequate time for the City to effectively analyze and prepare regulations to provide for appropriate permitting of enhanced services facilities.

The public hearing will allow the public to offer comments related to the City’s planning process for regulation of enhanced services facilities. This input will be forwarded to the Planning Commission for its consideration of appropriate amendments to the MMC.

RECOMMENDED ACTION: Conduct public hearing to allow for public comment concerning the planning process to consider amendments to the Marysville Municipal Code related to enhanced services facilities.
COUNCIL ACTION: No further City Council action is required following the close of the public hearing.

CITY OF MARYSVILLE
WASHINGTON

ORDINANCE NO. 3108

AN ORDINANCE OF THE CITY OF MARYSVILLE, WASHINGTON, ADOPTING INTERIM DEVELOPMENT REGULATIONS AMENDING TITLE 22A AND 22C OF THE MARYSVILLE MUNICIPAL CODE, TO SPECIFY THAT ENHANCED SERVICES FACILITIES AS DEFINED IN RCW 70.97 ARE NOT PERMITTED IN ANY ZONING DISTRICT WITHIN THE CITY OF MARYSVILLE; AND AMENDING CHAPTER 22A.020, DEFINITIONS, TO INCLUDE A DEFINITION OF ENHANCED SERVICES FACILITIES; AND AMENDING CHAPTER 22C.010, PERMITTED USES, AND CHAPTER 22C.020, PERMITTED USES, TO PROHIBIT ENHANCED SERVICES FACILITIES IN THE CITY OF MARYSVILLE; TO BE EFFECTIVE FOR A PERIOD OF SIX MONTHS; AND SETTING A DATE FOR A PUBLIC HEARING ON THE INTERIM DEVELOPMENT REGULATIONS, AND DECLARING AN EMERGENCY TO EXIST.

WHEREAS, chapter 70.97 RCW provides for the licensing, operations and management of Enhanced Services Facilities in the State of Washington; and

WHEREAS, RCW 70.97.010 defines the term "Enhanced Services Facility" as "a facility that provides support and services to persons for whom acute inpatient treatment is not medically necessary" (such facilities hereafter referred to in the plural as "Enhanced Services Facilities"); and

WHEREAS, Enhanced Services Facilities serve individuals 18 years of age or older with either a mental disorder, a substance use disorder, or co-occurring mental disorder and substance use disorder; and

WHEREAS, RCW 70.97.060 requires that all new facilities are required to meet all applicable state and local rules, regulations, permits, and code requirements; and

WHEREAS, RCW 70.97.090 specifically identifies the following "*residential uses*" as exempt from the Enhanced Services Facility regulations: nursing homes, assisted living facilities, adult family homes, facilities approved and certified under Chapter 71A.22 RCW, residential treatment facilities licensed under Chapter 71.12 RCW, and hospitals. Each of these uses are regulated by the State of Washington under separate state codes and are not treated as similar uses under state law; and

WHEREAS, the Marysville Municipal Code regulates the location and development of "Senior Citizen Assisted" dwellings, "Adult Family Homes," "Convalescent, Nursing or Retirement Homes," "Master Planned Senior Communities" and "Residential Care Facilities," but the current zoning code does not provide a

comparable land use definition for “Enhanced Services Facilities” or establish where such use may locate, or associated development standards; and

WHEREAS, the City Council understands that Enhanced Services Facilities are needed throughout the State of Washington, however without proper zoning controls, permitting of such a facility in the City of Marysville could result in potential negative impacts on the community; and

WHEREAS, the Council wishes to study the issue further and directs the Planning Commission to consider potential amendments to the Marysville Municipal Code regarding zoning regulations, permitting processes, and any conditions or standards that may be appropriate for Enhanced Services Facilities; and

WHEREAS, the City has determined that interim development regulations adopted under the provisions of RCW 36.70A.390 are necessary to allow adequate time for the City to effectively analyze and prepare regulations sufficient to provide for appropriate permitting of Enhanced Services Facilities; and

WHEREAS, the City has determined that interim development regulations are furthermore necessary to prevent vesting of any permit applications for Enhanced Services Facilities until such time as potential zoning regulations, permitting processes, and any conditions or standards that may be appropriate for Enhanced Services Facilities can be thoroughly reviewed and prepared; and

WHEREAS, pursuant to RCW 36.70A.390, the City Council will conduct a public hearing on the interim development regulations contained within this Ordinance in order to take public testimony and to consider further findings of fact.

NOW, THEREFORE, THE CITY COUNCIL OF THE CITY OF MARYSVILLE, WASHINGTON, DO ORDAIN AS FOLLOWS:

Section 1. Findings of Fact. The recitals set forth above are hereby adopted as the City Council’s initial findings of fact in support of the interim development regulations adopted herein. The City Council may, in its discretion, adopt additional findings after the public hearing referenced in Section 4 of this Ordinance.

Section 2. Interim Development Regulation. The City Council hereby adopts the interim development regulations as set forth in **Exhibit A** to this Ordinance, amending MMC 22A.020.060, MMC 22C.010.060, MMC 22C.010.070, MMC 22C.020.060, and MMC 22C.020.070.

Section 3. Duration. This interim development regulation shall be in effect for six (6) months following the effective date of this Ordinance.

Section 4. Public Hearing Required. As required by RCW 36.70A.390, within sixty (60) days of the passage of this ordinance, the City Council shall hold a public hearing on this ordinance in order to take public testimony and to consider further findings of fact. Said hearing shall be 7:00 p.m., Monday, December 14, 2020. The City Clerk is directed to provide notice of such public hearing as required by law.

Section 5. Declaration of Emergency. The City Council hereby declares that an emergency exists necessitating that this Ordinance take effect immediately upon passage by a majority vote plus one of the whole membership of the Council. Without an immediate adoption of the interim development regulations as set forth in **Exhibit A**, applications for Enhanced Services Facilities could become vested, leading to development that could be incompatible with the codes eventually adopted by the City. Therefore, the interim development regulations as set forth in **Exhibit A** must be adopted as an emergency measure to protect the public health, safety and welfare, and to prevent the submission of applications for Enhanced Services Facilities to the City in an attempt to vest rights for an indefinite period of time. This Ordinance does not affect any existing vested rights.

Section 6. Severability. If any section, subsection, sentence, clause, phrase, or word of this Ordinance should be held to be invalid or unconstitutional by a court of competent jurisdiction, such invalidity or unconstitutionality thereof shall not affect the validity or constitutionality of any other section, subsection, sentence, clause, phrase, or word of this Ordinance.

Section 7. Correction. Upon approval by the City Attorney, the City Clerk or the code reviser are authorized to make necessary corrections to this Ordinance, including scrivener's errors or clerical mistakes; references to other local, state, or federal laws, rules, or regulations; or numbering or referencing of ordinances or their sections and subsections.

Section 8. Effective Date. This ordinance shall take effect and be in full force and effect immediately upon passage, as set forth in Section 5, as long as it is approved by a majority plus one of the entire membership of the City Council, as required by RCW 35A.12.130. Pursuant to *Matson v. Clark County board of Commissioners*, 79 Wn. App. 641, 904 P.2d317 (1995), non-exhaustive underlying facts necessary to support this emergency declaration are included in the recitals, above, all of which are adopted by reference as findings of fact as if fully set forth herein.

PASSED AND APPROVED by the Marysville City Council this 23rd day of November, 2020.

CITY OF MARYSVILLE


Jon Nehring, Mayor

ATTEST:

By: 
Deputy City Clerk

APPROVED AS TO FORM:

By: , Esq.
Jon Walker, City Attorney

Date of Publication: November 27, 2020

Effective Date: December 2, 2020

Exhibit A

22A.020.060 “E” definitions.

“Easement” means a right granted by a property owner to specifically named parties or to the public for the use of certain land for specified purposes.

“Effective date” means the date a final decision becomes effective.

“EIS” means environmental impact statement.

“Elderly” means a person 62 years of age or older.

“Electric scooters and motorcycles” means any two-wheel vehicle that operates exclusively on electrical energy from an off-board source that is stored in the vehicle’s batteries and produces zero emissions or pollution when stationary or operating.

“Electric sign” means any sign containing electrical wiring, lighting, or other electrical components, but not including signs illuminated by a detached exterior light source.

“Electric vehicle” means any vehicle that operates, either partially or exclusively, on electrical energy from the grid, or an off-board source, that is stored on board for motive purpose. “Electric vehicle” includes:

- (1) A battery electric vehicle;
- (2) A plug-in hybrid electric vehicle;
- (3) A neighborhood electric vehicle; and
- (4) A medium-speed electric vehicle.

“Electric vehicle charging station” means a public or private parking space that is served by battery charging station equipment that has as its primary purpose the transfer of electric energy (by conductive or inductive means) to a battery or other energy storage device in an electric vehicle. An electric vehicle charging station equipped with Level 1 or Level 2 charging equipment is permitted outright as an accessory use to any principal use.

“Electric vehicle charging station – public” means an electric vehicle charging station that is:

- (1) Publicly owned and publicly available (e.g., park and ride parking, public library parking lot, on-street parking); or
- (2) Privately owned and publicly available (e.g., shopping center parking, nonreserved parking in multifamily parking lots).

“Electric vehicle charging station – restricted” means an electric vehicle charging station that is:

(1) Privately owned and restricted access (e.g., single-family home, executive parking, designated employee parking); or

(2) Publicly owned and restricted (e.g., fleet parking with no access to the general public).

“Electric vehicle infrastructure” means structures, machinery, and equipment necessary and integral to support an electric vehicle, including battery charging stations, rapid charging stations, and battery exchange stations.

“Electric vehicle parking space” means any marked parking space that identifies the use to be exclusively for the parking of an electric vehicle.

“Electronic message sign” means a variable message sign that utilizes computer-generated messages or some other electronic means of changing copy. These signs include displays using incandescent lamps, LEDs, LCDs or a flipper matrix. Also known as “changeable copy sign.”

“Elevated building (floodplain management)” means, for insurance purposes, a nonbasement building which has its lowest elevated floor raised above ground level by foundation walls, shear walls, posts, piers, pilings, or columns.

“Elevation certificate” means an administrative tool of the National Flood Insurance Program (NFIP) that can be used to provide elevation information, to determine the proper insurance premium rate, and to support a request for a letter of map amendment (LOMA) or letter of map revision based on fill (LOMR-F).

“Eligible facilities request” means any request for modification of an existing tower or base station that does not substantially change the physical dimensions of such tower or base station, involving:

(1) Co-location of new transmission equipment;

(2) Removal of transmission equipment; or

(3) Replacement of transmission equipment.

Criteria on what constitutes a substantial change is set forth in MMC [22C.250.210](#).

“Eligible support structure” means any existing tower or base station as defined in Chapter [22C.250](#) MMC; provided, that it is existing at the time an eligible facilities modification application is filed with the city.

“Emergency notification services” means services that notify the public of an emergency.

“Emergency services” means 911 emergency services and emergency notification services.

“Emergency support services” means information or database management services used in support of emergency services.

“Energy resource recovery facility” means an establishment for recovery of energy in a usable form from mass burning or refuse-derived fuel incineration, pyrolysis or any other means of using the heat

of combustion of solid waste.

"Engineering feasibility study" means a report prepared by a licensed professional engineer qualified by training to have expert engineering knowledge of a particular subject. The report will identify the capability of the land to withstand disturbance, such as erosion, sedimentation, geological hazards, or other aspects of the development.

"Enhanced Services Facility" means a facility that provides support and services to persons for whom acute inpatient treatment is not medically necessary and which typically serves individuals with either a mental disorder, a substance use disorder, or co-occurring mental disorder and substance use disorder. Such facilities shall be limited to a maximum 16 bed capacity and shall meet all of the regulatory and licensing requirements of the State of Washington per Chapter 70.97 RCW.

"Environmentally sensitive areas" means those areas regulated by Chapter 22E.010 MMC, and their buffers.

"Equipment, heavy" means high-capacity mechanical devices for moving earth or other materials, and mobile power units including, but not limited to:

- (1) Carryalls;
- (2) Graders;
- (3) Loading and unloading devices;
- (4) Cranes;
- (5) Drag lines;
- (6) Trench diggers;
- (7) Tractors;
- (8) Augers;
- (9) Bulldozers;
- (10) Concrete mixers and conveyers;
- (11) Harvesters;
- (12) Combines; or
- (13) Other major agricultural equipment and similar devices operated by mechanical power as distinguished from manpower.

"Erosion" means the wearing away of the earth's surface as a result of the movement of wind, rain, water and other natural agents which mobilize and transport soil particles.

“Erosion hazard areas” means lands or areas that, based on a combination of slope inclination and the characteristics of the underlying soils, are susceptible to varying degrees of risk of erosion. Erosion hazard areas are classified as low hazard, moderate hazard and high hazard, based on the following criteria:

(1) Low Hazard. Areas sloping less than 15 percent.

(2) Moderate Hazard. Areas sloping between 15 and 40 percent and underlain by soils that consist predominantly of silt, clay, bedrock or glacial till.

(3) High Hazard. Areas sloping between 15 and 40 percent that are underlain by soils consisting largely of sand and gravel, and all areas sloping more steeply than 40 percent.

“Evergreen” means a plant species with foliage that persists and remains green year-round.

“Ex parte communication” means any oral or written communication made by any person, including a city employee or official, pertaining to a matter that is or will be within the jurisdiction of the city council, hearing examiner or planning commission made outside of a public record.

Exceptions (Shoreline Master Program) – Requirements to Obtain Shoreline Permits or Local Reviews (Shoreline Master Program). Requirements to obtain a substantial development permit, conditional use permit, variance, letter of exemption, or other review to implement the shoreline management act do not apply to the following:

(1) Remedial Actions. Pursuant to RCW 90.58.355, any person conducting a remedial action at a facility pursuant to a consent decree, order, or agreed order pursuant to Chapter 70.105D RCW, or to the Department of Ecology when it conducts remedial action under Chapter 70.105D RCW.

(2) Boat Yard Improvements to Meet NPDES Permit Requirements. Pursuant to RCW 90.58.355, any person installing site improvements for storm water treatment in an existing boatyard facility to meet requirements of a National Pollutant Discharge Elimination System storm water general permit.

(3) WSDOT Facility Maintenance and Safety Improvements. Pursuant to RCW 90.58.356, Washington State Department of Transportation projects and activities meeting the conditions of RCW 90.58.356 are not required to obtain a substantial development permit, conditional use permit, variance, letter of exemption, or other local review.

(4) Projects consistent with an environmental excellence program agreement pursuant to RCW 90.58.045.

(5) Projects authorized through the Energy Facility Site Evaluation Council process, pursuant to Chapter 80.50 RCW.

Exemption (Shoreline Master Program). Certain specific developments as listed in WAC 173-27-040 as exempt from the definition of “substantial developments” are therefore exempt from the substantial development permit process of the SMA. An activity that is exempt from the substantial development provisions of the SMA must still be carried out in compliance with policies and standards of the Act and the local master program. Conditional use and/or variance permits may also still be required even though the activity does not need a substantial development permit. (RCW 90.58.030(3)(e); WAC 173-27-040.) “Exemption (shoreline master program)” also includes the

external retrofitting of an existing structure with the exclusive purpose of compliance with the Americans with Disabilities Act of 1990 (42 USC Sec. 12010 et seq.) or to otherwise provide physical access to the structure by individuals with disabilities.

“Existing and ongoing agricultural activities (small farms overlay zone)” means those activities involved in the production of crops and livestock, and changes between agricultural activities and uses, and normal operation, maintenance, repair, or reconstruction of existing serviceable structures, as well as construction of new farm structures, facilities or improved areas. An operation ceases to be ongoing when a formal plat has been approved by the city for development of the small farm.

“Existing and ongoing agricultural activities” means those activities involved in the production of crops and livestock, including but not limited to operation and maintenance of farm and stock ponds or drainage and irrigation systems, changes between agricultural activities and uses, and normal operation, maintenance, repair, or reconstruction of existing serviceable structures, facilities or improved areas. Activities which bring an area into agricultural use are not part of an ongoing activity. An operation ceases to be ongoing when the area on which it was conducted is proposed for conversion to a nonagricultural use or has lain idle for a period of longer than five years, unless the idle land is registered in a federal or state soils conservation program. Forest practices are not included in this definition.

“Existing manufactured home park or subdivision (floodplain management)” means a manufactured home park or subdivision for which the construction of facilities for servicing the lots on which the manufactured homes are to be affixed (including, at a minimum, the installation of utilities, the construction of streets, and either final site grading or the pouring of concrete pads) is completed before the effective date of the adopted floodplain management regulations.

“Existing (wireless communication facilities)” for purposes of Chapter 22C.250 MMC where it is related to a constructed tower or base station, means a constructed tower or base station that has been reviewed and approved under the applicable zoning or siting process or under another applicable state or local regulatory review process, and the term also includes a tower that was lawfully constructed but that was not reviewed and approved because it was not in a zoned area when it was built.

“Exotic species” means any species of plant or animal that is not indigenous to the area.

“Expansion to an existing manufactured home park or subdivision (floodplain management)” means the preparation of additional sites by the construction of facilities for servicing the lots on which the manufactured homes are to be affixed (including the installation of utilities, the construction of streets, and either final site grading or the pouring of concrete pads). (Ord. 3151 § 5, 2020; Ord. 3146 § 6, 2020; Ord. 3125 § 3 (Exh. B), 2019; Ord. 2852 § 10 (Exh. A), 2011).

22C.010.060 Permitted uses.

Specific Land Use	R-4.5	R-6.5	R-8	WR R-4-8	R-12	R-18	R-28	WR R-6- 18	R- MHP
Residential Land Uses									

Specific Land Use	R-4.5	R-6.5	R-8	WR R-4-8	R-12	R-18	R-28	WR R-6- 18	R- MHP
Dwelling Units, Types:									
Single detached (14)	P11	P11	P11	P11	P11	P11	P11	P11	P43
Model home	P30	P30	P30	P30	P30	P30	P30	P30	P30
Cottage housing (14)	C6	C6	C6	C6	C6	C6	C6	C6	
Duplex (14)	C8	P8	P8	P8	P	P	P	P	
Townhouse	P3	P3	P3	P3	P	P	P	P	
Multiple-family					P	P	P	P	
Mobile home	P12	P12	P12	P12	P12	P12	P12	P12	P12
Mobile/manufactured home park	P3	P3	P3		C	P	P		P45
Senior citizen assisted	C2	C2	C2	C2	C2	C2	C2	C2	C2
Factory-built	P7	P7	P7	P7	P7	P7	P7	P7	P7, 43
Recreational vehicle									P44
Group Residences:									
Adult family home	P	P	P	P	P	P	P	P	P
Convalescent, nursing, retirement	C2	C2	C2	C2	C2	C2	C2	C2	
Residential care facility	P	P	P	P	P	P	P	P	
Master planned senior community (15)	C	C	C	C	C	C	C	C	C
Accessory Uses:									
Residential accessory uses (1), (9), (10), (14), (49), (50)	P	P	P	P	P	P	P	P	P
Home occupation (5)	P	P	P	P	P13	P13	P13	P13	P
Temporary Lodging:									
Hotel/motel					P	P	P	P	
Bed and breakfast guesthouse (4)		C	C	C	P	P	P	P	
Bed and breakfast inn (4)					P	P	P	P	
Enhanced Services Facility (51)									
Recreation/Cultural Land Uses									
Park/Recreation:									
Park	P16	P16	P16	P16	P16	P16	P16	P16	P16
Recreational vehicle park									C46
Community center	C	C	C	C	C	C	C	C	C
Amusement/Entertainment:									
Sports club					C	C	C	C	
Golf facility (17)	C	C	C	C	P	P	P	P	

Specific Land Use	R-4.5	R-6.5	R-8	WR R-4-8	R-12	R-18	R-28	WR R-6- 18	R- MHP
Cultural:									
Library, museum and art gallery	C	C	C	C	C	C	C	C	C
Church, synagogue and temple	C	C	C	C	P	P	P	P	C
General Services Land Uses									
Personal Services:									
Funeral home/crematory	C18	C18	C18	C18	C18	C18	C18	C18	C18
Cemetery, columbarium or mausoleum	P24 C19	P24 C19	P24 C19	P24 C19	P24 C19	P24 C19	P24 C19	P24 C19	P24 C19
Day care I	P20	P20	P20	P20	P20	P20	P20	P20	P20
Day care II	C25	C25	C25	C25	C	C	C	C	C25
Stable	C	C	C	C					
Kennel or cattery, hobby	C	C	C	C	C	C	C	C	
Electric vehicle (EV) charging station (38), (39)	P	P	P	P	P	P	P	P	
EV rapid charging station (40), (41), (42)					P	P	P	P	
Health Services:									
Medical/dental clinic					C	C	C	C	
Supervised drug consumption facility									
Education Services:									
Elementary, middle/junior high, and senior high (including public, private and parochial)	C	C	C	C	C	C	C	C	C
Commercial school	C21	C21	C21	C21	C21	C21	C21	C21	
School district support facility	C23	C23	C23	C23	C23	C23	C23	C23	
Interim recycling facility	P22	P22	P22	P22	P22	P22	P22	P22	
Vocational school									
Government/Business Service Land Uses									
Government Services:									
Public safety facilities, including police and fire	C26	C26	C26	C26	C26	C26	C26	C26	C26
Utility facility	P	P	P	P	P	P	P	P	P
Private storm water management facility	P	P	P	P	P	P	P	P	P
Public storm water management facility	P	P	P	P	P	P	P	P	P
Business Services:									
Self-service storage (31)					C27	C27	C27	C27	
Professional office					C	C	C	C	
Automotive parking	P29	P29	P29	P29	P29	P29	P29	P29	
Model house sales office	P47	P47	P47	P47					

Specific Land Use	R-4.5	R-6.5	R-8	WR R-4-8	R-12	R-18	R-28	WR R-6-18	R- MHP
Wireless communication facility (28)	P C	P C	P C	P C	P C	P C	P C	P C	P C
State-Licensed Marijuana Facilities:									
Marijuana cooperative (48)									
Marijuana processing facility – Indoor only (48)									
Marijuana production facility – Indoor only (48)									
Marijuana retail facility (48)									
Retail/Wholesale Land Uses									
Forest products sales	P32	P32	P32	P32					
Agricultural crop sales	P32	P32	P32	P32					
Resource Land Uses									
Agriculture:									
Growing and harvesting crops	P34	P34	P34	P34					
Raising livestock and small animals	P35	P35	P35	P35					
Forestry:									
Growing and harvesting forest products	P34	P34	P34	P34					
Fish and Wildlife Management:									
Hatchery/fish preserve (33)	C	C	C	C					
Aquaculture (33)	C	C	C	C					
Regional Land Uses									
Regional storm water management facility	C	C	C	C	C	C	C	C	C
Nonhydroelectric generation facility	C	C	C	C	C	C	C	C	C
Transit park and pool lot	P	P	P	P	P	P	P	P	
Transit park and ride lot	C	C	C	C	C	C	C	C	
School bus base	C36	C36	C36	C36	C36	C36	C36	C36	
Racetrack	C37	C37	C37	C37	C37	C37	C37	C37	
College/university	C	C	C	C	C	C	C	C	

22C.010.070 Permitted uses – Development conditions.

(1) Accessory dwelling units must comply with development standards in Chapter 22C.180 MMC. Accessory dwelling units in the MHP zone are only allowed on single lots of record containing one single-family detached dwelling.

(2) Limited to three residents per the equivalent of each minimum lot size or dwelling units per acre allowed in the zone in which it is located.

(3) Only as part of a planned residential development (PRD) proposal, and subject to the same density as the underlying zone.

(4) Bed and breakfast guesthouses and inns are subject to the requirements and standards contained in Chapter 22C.210 MMC.

(5) Home occupations are subject to the requirements and standards contained in Chapter 22C.190 MMC.

(6) Subject to cottage housing provisions set forth in MMC 22C.010.280.

(7) Factory-built dwelling units shall comply with the following standards:

(a) A factory-built house must be inspected at least two times at the factory by the State Building Inspector during the construction process, and must receive an approval certifying that it meets all requirements of the International Building Code. At the building site, the city building official will conduct foundation, plumbing and final inspections.

(b) A factory-built house cannot be attached to a metal frame allowing it to be mobile. All such structures must be placed on a permanent foundation at the building site.

(8) Permitted outright in the R-6.5, R-8, and WR-R-4-8 zones on minimum 7,200-square-foot lots. A conditional use permit is required for the R-4.5 zone, and the minimum lot size must be 12,500 square feet. Duplexes must comply with the comprehensive plan density requirements for the underlying land use designation.

(9) A garage sale shall comply with the following standards:

(a) No residential premises shall have more than two such sales per year and no such sale shall continue for more than six days within a 15-day period.

(b) Signs advertising such sales shall not be attached to any public structures, signs or traffic control devices, nor to any utility poles. All such signs shall be removed 24 hours after the sale is completed.

A garage sale complying with the above conditions shall be considered as being an allowable accessory use to all residential land uses. A garage sale violating one or more of the above conditions shall be considered as being a commercial use and will be disallowed unless it complies with all requirements affecting commercial uses.

(10) Residential accessory structures must comply with development standards in Chapter 22C.180 MMC.

(11) Manufactured homes must:

(a) Be set on a permanent foundation, as specified by the manufacturer, enclosed with an approved concrete product from the bottom of the home to the ground which may be either load-bearing or decorative;

(b) Meet all design standards applicable to all other single-family homes in the neighborhood in which the manufactured home is to be located;

(c) Be no more than five years old, as evidenced by the date of manufacture recorded on the HUD data plate. An administrative variance to the requirement that a manufactured home be no more than five years old may be granted by the community development director only if the applicant demonstrates all of the following:

(i) The strict enforcement of the provisions of this title creates an unnecessary hardship to the property owner;

(ii) The proposed manufactured home is well maintained and does not present any health or safety hazards;

(iii) The variance is necessary or warranted because of the unique size, shape, topography, location, critical areas encumbrance, or other feature of the subject property;

(iv) The proposed manufactured home will be compatible with the neighborhood or area where it will be located;

(v) The subject property is otherwise deprived, by provisions of this title, of rights and privileges enjoyed by other properties in the vicinity and within an identical zone;

(vi) The need for the variance is not the result of deliberate actions of the applicant or property owner; and

(vii) The variance is the minimum necessary to grant relief to the applicant.

(12) Mobile homes are only allowed in existing mobile home parks established prior to October 16, 2006.

(13) Home occupations are limited to home office uses in multifamily dwellings. No signage is permitted in townhouse or multifamily dwellings.

(14) No more than one single-family detached or duplex dwelling is allowed per lot except in cottage housing developments that are developed with all cottages located on a common lot, and accessory dwelling units through the provisions of Chapter 22C.180 MMC.

(15) Subject to Chapter 22C.220 MMC, Master Planned Senior Communities.

(16) The following conditions and limitations shall apply, where appropriate:

(a) Parks are permitted in residential and mixed use zones when reviewed as part of a subdivision, mobile/manufactured home park, or multiple-family development proposal; otherwise, a conditional use permit is required;

(b) Lighting for structures and fields shall be directed away from residential areas; and

(c) Structures or service yards shall maintain a minimum distance of 50 feet from property lines adjoining residential zones.

(17) Golf facilities shall comply with the following:

(a) Structures, driving ranges and lighted areas shall maintain a minimum distance of 50 feet from property lines adjoining residential zones.

(b) Restaurants are permitted as an accessory use to a golf course.

(18) Only as an accessory to a cemetery.

(19) Structures shall maintain a minimum distance of 100 feet from property lines adjoining residential zones.

(20) Only as an accessory to residential use and subject to the criteria set forth in Chapter 22C.200 MMC.

(21) Only as an accessory to residential use, provided:

(a) Students are limited to 12 per one-hour session;

(b) All instruction must be within an enclosed structure; and

(c) Structures used for the school shall maintain a distance of 25 feet from property lines adjoining residential zones.

(22) Limited to drop box facilities accessory to a public or community use such as a school, fire station or community center.

(23) Only when adjacent to an existing or proposed school.

(24) Limited to columbariums accessory to a church; provided, that existing required landscaping and parking are not reduced.

(25) Day care IIs must be located on sites larger than one-half acre and are subject to minimum standards identified in Chapter 22C.200 MMC for day care I facilities. Parking facilities and loading areas shall be located to the rear of buildings or be constructed in a manner consistent with the surrounding residential character. Evaluation of site suitability shall be reviewed through the conditional use permit process.

(26) Public safety facilities, including police and fire, shall comply with the following:

(a) All buildings and structures shall maintain a minimum distance of 20 feet from property lines adjoining residential zones;

(b) Any buildings from which fire-fighting equipment emerges onto a street shall maintain a distance of 35 feet from such street.

(27) Accessory to an apartment development of at least 12 units, provided:

(a) The gross floor area in self-service storage shall not exceed 50 percent of the total gross floor area of the apartment dwellings on the site;

(b) All outdoor lights shall be deflected, shaded and focused away from all adjoining property;

(c) The use of the facility shall be limited to dead storage of household goods;

(d) No servicing or repair of motor vehicles, boats, trailers, lawn mowers or similar equipment;

(e) No outdoor storage or storage of flammable liquids, highly combustible or explosive materials or hazardous chemicals;

(f) No residential occupancy of the storage units;

(g) No business activity other than the rental of storage units to the apartment dwellings on the site; and

(h) A resident manager shall be required on the site and shall be responsible for maintaining the operation of the facility in conformance with the conditions of approval.

(28) All WCFs and modifications to WCFs are subject to Chapter 22C.250 MMC including, but not limited to, the siting hierarchy, MMC 22C.250.060. WCFs may be a permitted use or a conditional use subject to MMC 22C.250.040.

(29) Limited to commuter parking facilities for users of transit, carpools or ride-share programs, provided:

(a) They are located on existing parking lots for churches, schools, or other permitted nonresidential uses which have excess capacity available during commuting hours; and

(b) The site is adjacent to a designated arterial that has been improved to a standard acceptable to the department.

(30) Model Homes.

(a) The community development director may approve construction of model homes subject to the following conditions:

(i) No model home shall be constructed without the issuance of a building permit;

(ii) In no event shall the total number of model homes in a preliminary subdivision be greater than nine;

(iii) A hard-surfaced roadway to and abutting all model homes shall be constructed to standards determined by the city engineer or designee;

(iv) Operational fire hydrant(s) must be available in accordance with the International Fire Code;

(v) Submittal of a site plan, stamped by a registered civil engineer or licensed surveyor, delineating the location of each structure relative to existing and proposed utilities, lot lines, easements, roadways, topography and critical areas;

(vi) Submittal of building permit applications for each of the proposed structures;

(vii) Approval of water, sewer and storm sewer extension plans to serve the proposed structures; and

(viii) Execution of an agreement with the city saving and holding it harmless from any damages, direct or indirect, as a result of the approval of the construction of model homes on the site.

(b) Prior to occupancy of any model home, the final plat of the subject subdivision shall be approved and recorded.

(31) Any outdoor storage areas are subject to the screening requirements of the landscape code.

(32) Subject to approval of a small farms overlay zone.

(33) May be further subject to the provisions of the Marysville shoreline master program.

(34) Only allowed in conjunction with the small farms overlay zone.

(35) Provided, that the property has received approval of a small farms overlay designation, or is larger than one acre in size.

(36) Only in conjunction with an existing or proposed school.

(37) Except racing of motorized vehicles.

(38) Level 1 and Level 2 charging only.

(39) Allowed only as an accessory use to a principal outright permitted use or permitted conditional use.

(40) The term "rapid" is used interchangeably with "Level 3" and "fast charging."

(41) Only "electric vehicle charging stations – restricted" as defined in Chapter 22A.020 MMC.

(42) Rapid (Level 3) charging stations are required to be placed within a parking garage.

(43) One single-family detached dwelling per existing single lot of record. Manufactured homes on single lots must meet the criteria outlined in subsection (11) of this section.

(44) Used as a permanent residence in an established MHP or RV park; provided, that utility hookups in MHPs meet current standards for MHPs or RV parks.

(45) MHPs shall fulfill the requirements of Chapter 22C.230 MMC.

(46) Recreational vehicle parks are subject to the requirements and conditions of Chapter 22C.240 MMC.

(47) Model house sales offices are subject to the requirements of MMC 22C.110.030(12).

(48) No person or entity may produce, grow, manufacture, process, accept donations for, give away, or sell marijuana concentrates, marijuana-infused products, or usable marijuana within residential zones in the city. Provided, activities in strict compliance with RCW 69.51A.210 and 69.51A.260 are not a violation of the Marysville Municipal Code.

(49) Shipping/cargo and similar storage containers are prohibited on lots within a platted subdivision and properties under one acre in size. Shipping/cargo and similar storage containers may be located on properties over one acre in size if located behind the primary residence, observe all setbacks applicable to an accessory structure, and are screened from public view.

(50) Accessory structures may not be utilized as, or converted to, a dwelling unless the structure complies with the accessory dwelling unit standards outlined in MMC 22C.180.030.

(51) Enhanced Services Facilities are prohibited in all residential zones as such are identified and adopted in chapter 22C.010 MMC.

22C.020.060 Permitted uses.

Specific Land Use	NB	CB	CB-WR	GC	DC	MU (63)	LI	GI	REC	P/I
Residential Land Uses										
Dwelling Units, Types:										
Townhouse					P6	P				
Multiple-family	C4	P4, C5		P4, C5	P4, P6	P				
Mobile home	P7	P7	P7	P7	P7	P7	P7	P7		
Senior citizen assisted	P					C				P
Caretaker's quarters (3)	P	P	P	P	P	P	P	P	P	P
Group Residences:										
Adult family home (70)	P	P	P	P	P	P				P
Convalescent, nursing, retirement	C	P			P	P				P

Specific Land Use	NB	CB	CB-WR	GC	DC	MU (63)	LI	GI	REC	P/I
Residential care facility	P	P			P	P	P70	P70	P70	P
Master planned senior community (10)						C				C
Enhanced Services Facility (77)										
Accessory Uses:										
Home occupation (2)	P8	P8, P9	P8, P9	P8, P9	P8, P9	P8, P9	P9	P9		
Temporary Lodging:										
Hotel/motel	P	P	P	P	P	P	P75			
Bed and breakfast guesthouse (1)										
Bed and breakfast inn (1)	P	P	P	P						
Recreation/Cultural Land Uses										
Park/Recreation:										
Park	P11	P	P	P	P	P	P	P	P11	P
Marina					P			P	C	P
Dock and boathouse, private, noncommercial					P			P	P16	P
Recreational vehicle park				C12			C12		C	P
Boat launch, commercial or public					P			P		P
Boat launch, noncommercial or private					P			P	P17	P
Community center	P	P	P	P	P	P	P	P	P	P
Amusement/Entertainment:										
Theater		P	P	P	P	P				
Theater, drive-in				C						
Amusement and recreation services		P18	P18	P18	P18	P19	P	C		
Sports club	P	P	P	P	P	P	P	P		
Golf facility (13)		P	P	P			P	P	C	
Shooting range (14)				P15			P15			
Outdoor performance center				C			C		C	C
Riding academy							P		C	
Cultural:										
Library, museum and art gallery	P	P	P	P	P	P	P	P	C	P
Church, synagogue and temple	P	P	P	P	P	P	P	P		P
Dancing, music and art center		P	P	P	P	P			C	P
General Services Land Uses										
Personal Services:										
General personal service	P	P	P	P	P	P	P	P		

Specific Land Use	NB	CB	CB-WR	GC	DC	MU (63)	LI	GI	REC	P/I
Dry cleaning plant		P	P				P	P		
Dry cleaning pick-up station and retail service	P	P	P	P	P	P25	P76	P		
Funeral home/crematory		P	P	P	P	P26	P76	P		
Cemetery, columbarium or mausoleum	P24	P24	P24	P24, C20			P	P		
Day care I	P70	P70	P70	P70	P70	P70	P21, 70	P70	P70	P70
Day care II	P	P	P	P	P	P	P21			
Veterinary clinic	P	P	P	P	P	P	P76	P		
Automotive repair and service	P22	C, P28	C, P28	P			P	P		
Electric vehicle (EV) charging station (64)	P	P	P	P	P	P	P	P	P	P
EV rapid charging station (65), (66)	P	P	P	P	P67	P67	P	P		
EV battery exchange station				P			P	P		
Miscellaneous repair		P	P	P			P	P		
Social services		P	P	P	P	P				P
Kennel, commercial and exhibitor/breeding (71)		P	P	P			P	P		
Pet daycare (71), (72)		P	P	P	P	P	P76	P		
Civic, social and fraternal association		P	P	P	P	C		P		P
Club (community, country, yacht, etc.)								P		P
Health Services:										
Medical/dental clinic	P	P	P	P	P	P				P
Hospital		P	P	P	P	C				C
Miscellaneous health	P68	P68	P68	P68	P68	P68				P68
Supervised drug consumption facility										
Education Services:										
Elementary, middle/junior high, and senior high (including public, private and parochial)		C	C	C	C	C	P	C		C
Commercial school	P	P	P		P	P27				C
School district support facility	C	P	P	P	P	P	P	P		P
Vocational school		P	P	P	P	P27				P
Government/Business Service Land Uses										
Government Services:										
Public agency office	P	P	P	P	P	P	P	P		P
Public utility yard				P			P			P
Public safety facilities, including police and fire	P29	P	P	P	P	P	P			P

Specific Land Use	NB	CB	CB-WR	GC	DC	MU (63)	LI	GI	REC	P/I
Utility facility	P	P	P	P		C	P	P		P
Private storm water management facility	P	P	P	P	P	P	P	P		P
Public storm water management facility	P	P	P	P	P	P	P	P		P
Business Services:										
Contractors' office and storage yard				P30	P30	P30	P	P		
Interim recycling facility		P23	P23	P23			P			P
Taxi stands		P	P	P			P	P		
Trucking and courier service		P31	P31	P31			P	P		
Warehousing and wholesale trade				P			P	P		
Mini-storage (36)							P76	P		
Freight and cargo service				P			P	P		
Cold storage warehousing							P	P		
General business service and office	P	P	P	P	P	P30	P	P		
Commercial vehicle storage							P	P		
Professional office	P	P	P	P	P	P	P			
Miscellaneous equipment rental		P30, 37	P30, 37	C38		P30, 37	P	P		
Automotive rental and leasing				P			P	P		
Automotive parking	P	P	P	P	P	P	P	P		
Research, development and testing				P			P	P		
Heavy equipment and truck repair							P	P		
Automobile holding yard				C			P	P		
Commercial/industrial accessory uses (73)	P39, 40	P39	P39	P39	P39, 40	P39, 40	P	P		
Adult facility								P33		
Factory-built commercial building (35)	P	P	P	P	P		P	P		
Wireless communication facility (32)	P, C	P, C	P, C	P, C	P, C	P, C	P, C	P, C		P, C
State-Licensed Marijuana Facilities:										
Marijuana cooperative (69)										
Marijuana processing facility – Indoor only (69)										
Marijuana production facility – Indoor only (69)										
Marijuana retail facility (69)										
Retail/Wholesale Land Uses										
Building, hardware and garden materials	P47	P	P	P	P	P47	P76	P		
Forest products sales		P	P	P			P			

Specific Land Use	NB	CB	CB-WR	GC	DC	MU (63)	LI	GI	REC	P/I
Department and variety stores	P	P	P	P	P	P	P76			
Food stores	P	P	P	P	P	P45	P76			
Agricultural crop sales		P	P	P		C	P76			
Storage/retail sales, livestock feed							P76	P		
Motor vehicle and boat dealers		P	P	P			P	P		
Motorcycle dealers		C	C	P	P49		P	P		
Gasoline service stations	P	P	P	P	P		P76	P		
Eating and drinking places	P41	P	P	P	P	P46	P46	P		
Drug stores	P	P	P	P	P	P	P76	P		
Liquor stores		P	P	P						
Used goods: antiques/secondhand shops		P	P	P	P	P				
Sporting goods and related stores		P	P	P	P	P				
Book, stationery, video and art supply stores	P	P	P	P	P	P				
Jewelry stores		P	P	P	P	P				
Hobby, toy, game shops	P	P	P	P	P	P				
Photographic and electronic shops	P	P	P	P	P	P				
Fabric and craft shops	P	P	P	P	P	P				
Fuel dealers				P43			P43	P43		
Florist shops	P	P	P	P	P	P				
Pet shops	P	P	P	P	P	P				
Tire stores		P	P	P	P		P76	P		
Bulk retail		P	P	P			P76			
Auction houses				P42			P76			
Truck and heavy equipment dealers							P	P		
Mobile home and RV dealers				C			P	P		
Retail stores similar to those otherwise named on this list	P	P	P	P	P	P48	P44, 76	P44		
Automobile wrecking yards							C	P		
Manufacturing Land Uses										
Food and kindred products		P50, 52	P50, 52	P50			P50	P		
Winery/brewery		P53	P53	P	P53	P53	P	P		
Textile mill products							P	P		
Apparel and other textile products				C			P	P		
Wood products, except furniture				P			P	P		
Furniture and fixtures				P			P	P		

Specific Land Use	NB	CB	CB-WR	GC	DC	MU (63)	LI	GI	REC	P/I
Paper and allied products							P	P		
Printing and publishing	P51	P51	P51	P		P51	P	P		
Chemicals and allied products							C	C		
Petroleum refining and related industries							C	C		
Rubber and misc. plastics products							P	P		
Leather and leather goods							C	C		
Stone, clay, glass and concrete products							P	P		
Primary metal industries							C	P		
Fabricated metal products				C			P	P		
Industrial and commercial machinery							C	P		
Heavy machinery and equipment							C	P		
Computer and office equipment				C			P			
Electronic and other electric equipment				C			P			
Railroad equipment							C	P		
Miscellaneous light manufacturing				P54, 74	P54		P	P		
Motor vehicle and bicycle manufacturing							C	P		
Aircraft, ship and boat building							C	P		
Tire retreading							C	P		
Movie production/distribution				P			P			
Resource Land Uses										
Agriculture:										
Growing and harvesting crops							P	P	P	
Raising livestock and small animals							P	P	P	
Greenhouse or nursery, wholesale and retail				P			P	P	C	
Farm product processing							P	P		
Forestry:										
Growing and harvesting forest products							P			
Forest research							P			
Wood waste recycling and storage							C	C		
Fish and Wildlife Management:										
Hatchery/fish preserve (55)							P	P	C	
Aquaculture (55)							P	P	C	
Wildlife shelters	C	C	C						P	
Mineral:										

Specific Land Use	NB	CB	CB-WR	GC	DC	MU (63)	LI	GI	REC	P/I
Processing of minerals							P	P		
Asphalt paving mixtures and block							P	P		
Regional Land Uses										
Jail		C	C	C			C			
Regional storm water management facility		C	C	C	C		C	C		P
Public agency animal control facility				C			P	P		C
Public agency training facility		C56	C56	C56		C56	C57			C57
Nonhydroelectric generation facility	C	C	C	C			C	C		C
Energy resource recovery facility							C			
Soil recycling/incineration facility							C	C		
Solid waste recycling								C		C
Transfer station							C	C		C
Wastewater treatment facility							C	C		C
Transit bus base				C			P			C
Transit park and pool lot	P	P	P	P	P	P	P	P		P
Transit park and ride lot	P	P	P	P	P	P	P	P		C
School bus base	C	C	C	C			P			C58
Racetrack	C59	C59	C59	C			P			
Fairground							P	P		C
Zoo/wildlife exhibit		C	C	C						C
Stadium/arena				C			C	P		C
College/university	C	P	P	P	P	P	P	P		C
Secure community transition facility								C60		
Opiate substitution treatment program facilities		P61, 62	P61, 62	P61, 62	P61, 62		P62	P62		

22C.020.070 Permitted uses – Development conditions.

(1) Bed and breakfast guesthouses and inns are subject to the requirements and standards contained in Chapter 22C.210 MMC, Bed and Breakfasts.

(2) Home occupations are subject to the requirements and standards contained in Chapter 22C.190 MMC, Home Occupations.

(3) Limited to one dwelling unit for the purposes of providing on-site service and security of a commercial or industrial business. Caretaker's quarters are subject to the provisions set forth in Chapter 22C.110 MMC, entitled "Temporary Uses."

- (4) All units must be located above a street-level commercial use.
- (5) Twenty percent of the units, but no more than two total units, may be located on the street level of a commercial use, if conditional use permit approval is obtained and the units are designed exclusively for ADA accessibility. The street-level units shall be designed so that the units are not located on the street front and primary access is towards the rear of the building.
- (6) Permitted on the ground floor in the southwest sector of downtown vision plan area, as incorporated into the city of Marysville comprehensive plan.
- (7) Mobile homes are only allowed in existing mobile home parks established prior to October 16, 2006.
- (8) Home occupations are limited to home office uses in multifamily dwellings. No signage is permitted in townhouse or multifamily dwellings.
- (9) Permitted in a legal nonconforming or conforming residential structure.
- (10) Subject to Chapter 22C.220 MMC, Master Planned Senior Communities.
- (11) The following conditions and limitations shall apply, where appropriate:
 - (a) Parks are permitted in residential and mixed use zones when reviewed as part of a subdivision or multiple-family development proposal; otherwise, a conditional use permit is required;
 - (b) Lighting for structures and fields shall be directed away from residential areas; and
 - (c) Structures or service yards shall maintain a minimum distance of 50 feet from property lines adjoining residential zones.
- (12) Recreational vehicle parks are subject to the requirements and conditions of Chapter 22C.240 MMC.
- (13) Golf Facility.
 - (a) Structures, driving ranges and lighted areas shall maintain a minimum distance of 50 feet from property lines adjoining residential zones.
 - (b) Restaurants are permitted as an accessory use to a golf course.
- (14) Shooting Range.
 - (a) Structures and ranges shall maintain a minimum distance of 50 feet from property lines adjoining residential zones;
 - (b) Ranges shall be designed to prevent stray or ricocheting projectiles or pellets from leaving the property; and

(c) Site plans shall include safety features of the range; provisions for reducing noise produced on the firing line; and elevations of the range showing target area, backdrops or butts.

(15) Only in an enclosed building.

(16) Dock and Boathouse, Private, Noncommercial.

(a) The height of any covered over-water structure shall not exceed 20 feet as measured from the line of ordinary high water;

(b) The total roof area of covered, over-water structures shall not exceed 1,000 square feet;

(c) The entirety of such structures shall have not greater than 50 percent of the width of the lot at the natural shoreline upon which it is located;

(d) No over-water structure shall extend beyond the average length of all pre-existing over-water structures along the same shoreline and within 300 feet of the parcel on which proposed. Where no such pre-existing structures exist within 300 feet, the pier length shall not exceed 50 feet;

(e) Structures permitted hereunder shall not be used as a dwelling; and

(f) Covered structures are subject to a minimum setback of five feet from any side lot line or extension thereof. No setback from adjacent properties is required for any uncovered structure, and no setback from water is required for any structure permitted hereunder.

(17) Boat Launch, Noncommercial or Private.

(a) The city may regulate, among other factors, required launching depth, and length of docks and piers;

(b) Safety buoys shall be installed and maintained separating boating activities from other water-oriented recreation and uses where this is reasonably required for public safety, welfare and health; and

(c) All site improvements for boat launch facilities shall comply with all other requirements of the zone in which it is located.

(18) Excluding racetrack operation.

(19) Amusement and recreation services shall be a permitted use if they are located within an enclosed building, or a conditional use if located outside. In both instances they would be subject to the exclusion of a racetrack operation similar to other commercial zones.

(20) Structures shall maintain a minimum distance of 100 feet from property lines adjoining residential zones.

(21) Permitted as an accessory use; see MMC 22A.020.020, the definition of "Accessory use, commercial/industrial."

(22) Only as an accessory to a gasoline service station; see retail and wholesale permitted use table in MMC 22C.020.060.

(23) All processing and storage of material shall be within enclosed buildings and excluding yard waste processing.

(24) Limited to columbariums accessory to a church; provided, that existing required landscaping and parking are not reduced.

(25) Drive-through service windows in excess of one lane are prohibited in Planning Area 1.

(26) Limited to columbariums accessory to a church; provided, that existing required landscaping and parking are not reduced.

(27) All instruction must be within an enclosed structure.

(28) Car washes shall be permitted as an accessory use to a gasoline service station.

(29) Public Safety Facilities, Including Police and Fire.

(a) All buildings and structures shall maintain a minimum distance of 20 feet from property lines adjoining residential zones;

(b) Any buildings from which fire-fighting equipment emerges onto a street shall maintain a distance of 35 feet from such street.

(30) Outdoor storage of materials or vehicles must be accessory to the primary building area and located to the rear of buildings. Outdoor storage is subject to an approved landscape plan that provides for effective screening of storage, so that it is not visible from public right-of-way or neighboring properties.

(31) Limited to self-service household moving truck or trailer rental accessory to a gasoline service station.

(32) All WCFs and modifications to WCFs are subject to Chapter 22C.250 MMC including but not limited to the siting hierarchy, MMC 22C.250.060. WCFs may be a permitted use or a CUP may be required subject to MMC 22C.250.040.

(33) Subject to the conditions and requirements listed in Chapter 22C.030 MMC.

(34) Reserved.

(35) A factory-built commercial building may be used for commercial purposes subject to the following requirements:

(a) A factory-built commercial building must be inspected at least two times at the factory by the State Building and Electrical Inspector during the construction process, and must receive a state approval stamp certifying that it meets all requirements of the International Building and

Electrical Codes. At the building site, the city building official will conduct foundation, plumbing and final inspections; and

(b) A factory-built commercial building cannot be attached to a metal frame allowing it to be mobile. All structures must be placed on a permanent, poured-in-place foundation. The foundation shall be structurally engineered to meet the requirements set forth in Chapter 16 of the International Building Code.

(36) Mini-storage facilities are subject to the development standards outlined in Chapter 22C.170 MMC.

(37) Except heavy equipment.

(38) With outdoor storage and heavy equipment.

(39) Incidental assembly shall be permitted; provided, it is limited to less than 20 percent of the square footage of the site excluding parking.

(40) Light industrial uses may be permitted; provided, there is no outdoor storage of materials, products or vehicles.

(41) Excluding drinking places such as taverns and bars and adult entertainment facilities.

(42) Excluding vehicle and livestock auctions.

(43) If the total storage capacity exceeds 6,000 gallons, a conditional use permit is required.

(44) The retail sale of products manufactured on site shall be permitted; provided, that not more than 20 percent of the constructed floor area in any such development may be devoted to such retail use.

(45) Limited to 5,000 square feet or less.

(46) Eating and Drinking Places.

(a) Limited to 4,000 square feet or less.

(b) Drive-through service windows in excess of one lane are prohibited in Planning Area 1.

(c) Taverns, bars, lounges, etc., are required to obtain a conditional use permit in the mixed use zone.

(47) Limited to hardware and garden supply stores.

(48) Limited to convenience retail, such as video, and personal and household items.

(49) Provided there is no outdoor storage and/or display of any materials, products or vehicles.

(50) Except slaughterhouses.

- (51) Limited to photocopying and printing services offered to the general public.
- (52) Limited to less than 10 employees.
- (53) In conjunction with an eating and drinking establishment.
- (54) Provided there is no outdoor storage and/or display of any materials, products or vehicles.
- (55) May be further subject to the provisions of city of Marysville shoreline management program.
- (56) Except weapons armories and outdoor shooting ranges.
- (57) Except outdoor shooting ranges.
- (58) Only in conjunction with an existing or proposed school.
- (59) Except racing of motorized vehicles.
- (60) Limited to land located along east side of 47th Avenue NE alignment, in the east half of the northeast quarter of Section 33, Township 30N, Range 5E, W.M., and in the northeast quarter of the southeast quarter of Section 33, Township 30N, Range 5E, W.M., and land located east side of SR 529, north of Steamboat Slough, south and west of Ebey Slough (a.k.a. TP No. 300533-002-004-00) and in the northwest and southwest quarters of Section 33, Township 30N, Range 5E, W.M., as identified in Exhibit A, attached to Ordinance No. 2452.
- (61) Opiate substitution treatment program facilities permitted within commercial zones are subject to Chapter 22G.070 MMC, Siting Process for Essential Public Facilities.
- (62) Opiate substitution treatment program facilities, as defined in MMC 22A.020.160, are subject to the standards set forth below:
- (a) Shall not be established within 300 feet of an existing school, public playground, public park, residential housing area, child-care facility, or actual place of regular worship established prior to the proposed treatment facility.
 - (b) Hours of operation shall be restricted to no earlier than 6:00 a.m. and no later than 7:00 p.m. daily.
 - (c) The owners and operators of the facility shall be required to take positive ongoing measures to preclude loitering in the vicinity of the facility.
- (63) Permitted uses include Whiskey Ridge zones.
- (64) Level 1 and Level 2 charging only.
- (65) The term "rapid" is used interchangeably with Level 3 and fast charging.
- (66) Rapid (Level 3) charging stations are required to comply with the design and landscaping standards outlined in MMC 22C.020.265.

(67) Rapid (Level 3) charging stations are required to be placed within a parking garage.

(68) Excepting "marijuana (cannabis) dispensaries," "marijuana (cannabis) collective gardens," and "marijuana cooperatives" as those terms are defined or described in this code and/or under state law; such facilities and/or uses are prohibited in all zoning districts of the city of Marysville.

(69) No person or entity may produce, grow, manufacture, process, accept donations for, give away, or sell marijuana concentrates, marijuana-infused products, or usable marijuana within commercial, industrial, recreation, and public institution zones in the city. Provided, activities in strict compliance with RCW 69.51A.210 and 69.51A.260 are not a violation of the Marysville Municipal Code.

(70) Permitted within existing legal nonconforming single-family residences.

(71) Subject to the requirements set forth in MMC 10.04.460.*

(72) Pet daycares are restricted to indoor facilities with limited, supervised access to an outdoor fenced yard. Overnight boarding may be permitted as a limited, incidental use. Both outdoor access and overnight boarding privileges may be revoked or modified if the facility is not able to comply with the noise standards set forth in WAC 173-60-040.*

(73) Shipping/cargo and similar storage containers may be installed on commercial or industrial properties provided they are screened from public view pursuant to MMC 22C.120.160, Screening and impact abatement.

(74) Tanks, generators, and other machinery which does not generate nuisance noise may be located in the service/loading area. Truck service/loading areas shall not face the public street and shall be screened from the public street.

(75) Hotels/motels are prohibited within Arlington Airport Inner Safety Zones (ISZ) 2, 3, and 4. Hotel/motels that are proposed to locate within Arlington Airport Protection Subdistricts B and C shall be required to coordinate with the Arlington Municipal Airport to ensure that height, glare, and other aspects of the hotels/motels are compatible with air traffic and airport operations.

(76) Use limited to properties that have property frontage along State Avenue/Smokey Point Boulevard.

(77) Enhanced Services Facilities are prohibited in all commercial and industrial zones as such are identified and adopted in chapter 22C.020 MMC.