

**CITY OF MARYSVILLE AGENDA BILL**  
**EXECUTIVE SUMMARY FOR ACTION**

**CITY COUNCIL MEETING DATE: April 5, 2021 Briefing; April 12, 2021 Action**

<b>AGENDA ITEM:</b>	
Ordinance amending the Unified Development Code to allow “mini-storage” as a Conditional Use under limited circumstances in the Community Business and General Commercial zones	
<b>PREPARED BY:</b>	<b>DIRECTOR APPROVAL:</b>
Allan Giffen, Interim Community Development Director	<i>Allan Giffen</i> , Interim Director
<b>DEPARTMENT:</b>	
Community Development	
<b>ATTACHMENTS:</b>	
1. Ordinance	
<b>BUDGET CODE:</b>	<b>AMOUNT:</b>
N/A	N/A
<b>SUMMARY:</b>	

The Planning Commission has recommended an amendment to the Unified Development Code to allow the establishment of mini-storage as a Conditional Use on a limited basis in the CB Community Business and GC General Commercial zones. The proposed amendment would apply only to an area located north of 100<sup>th</sup> Street NE, east of Interstate 5, and west of 47<sup>th</sup> Avenue NE. It would also be limited to properties without direct frontage on an arterial street, and that have access constraints that do not support retail, office or other permitted commercial uses.

The Conditional Use process will ensure notice to surrounding property owners.

The recommendation from the Planning Commission includes amendments to the existing standards for mini-storage uses.

Background information, including staff memos to the Planning Commission and the minutes from Planning Commission meetings on this item, can be found at the following link:

[CC Agenda Bill Mini Storage documents](#)

**RECOMMENDED ACTION:**

Staff recommends that Council approve Ordinance No. \_\_\_\_, amending the Marysville Municipal Code to allow “mini-storage” as a Conditional Use under limited circumstances in the Community Business and General Commercial zones.

**RECOMMENDED MOTION:**

I move to approve Ordinance No. \_\_\_\_, amending the Marysville Municipal Code to allow “mini-storage” as a Conditional Use under limited circumstances in the Community Business and General Commercial zones.

**CITY OF MARYSVILLE  
WASHINGTON**

**ORDINANCE NO. \_\_\_\_\_**

**AN ORDINANCE OF THE CITY OF MARYSVILLE, WASHINGTON, UPDATING TITLE 22C OF THE MARYSVILLE MUNICIPAL CODE, TO SPECIFY THAT MINI-STORAGE SHALL BE ALLOWED UNDER LIMITED CIRCUMSTANCES AS A CONDITIONAL USE IN THE CB COMMUNITY BUSINESS AND GC GENERAL COMMERCIAL ZONES; AMENDING MMC 22C.020.060, PERMITTED USES, AMENDING MMC 22C.020.070, PERMITTED USES – DEVELOPMENT CONDITIONS, AND AMENDING MMC 22C.170, DESIGN CONSIDERATIONS.**

**WHEREAS**, the State Growth Management Act, Chapter 36.70A RCW mandates that cities periodically review and amend development regulations, including zoning ordinances and official controls; and

**WHEREAS**, RCW 36.70A.106 requires the processing of amendments to the City's development regulations in the same manner as the original adoption of the City's comprehensive plan and development regulations; and

**WHEREAS**, the State Growth Management Act requires notice and broad public participation when adopting or amending the City's comprehensive plan and development regulations; and

**WHEREAS**, the City, in reviewing and amending its development regulations has complied with the notice, public participation, and processing requirements established by the Growth Management Act, as more fully described below; and

**WHEREAS**, the City Council of the City of Marysville finds that from time to time it is necessary and appropriate to review and revise provisions of the City's municipal code and development code (MMC Title 22); and

**WHEREAS**, the Marysville Municipal Code regulates the location and development of "mini-storage" facilities; and

**WHEREAS**, the Planning Commission has initiated a review of potential amendments to the Marysville Municipal Code to allow mini-storage facilities as a Conditional Use under limited circumstances in the CB Community Business and GC General Commercial zones; and

**WHEREAS**, the Planning Commission held public work sessions on December 8, 2020, January 12, 2021, and February 9, 2021, to review the proposed amendments, including alternatives, and did hear and consider public comments; and

**WHEREAS**, the proposed amendments were submitted to the State of Washington Department of Commerce for 60-day review on February 1, 2021, in accordance with RCW 36.70A.106; and

**WHEREAS**, the proposed amendments to MMC Sections 22C.010.060, 22C.010.070, 22C.180.030, 22C.110.020, and 22C.110.030 are exempt from State Environmental Policy Act review under WAC 197-11-800(19)<sup>[BE1]</sup>; and

**WHEREAS**, the Planning Commission held a duly-advertised public hearing on February 23, 2021, and received testimony from City staff and the public; and

**WHEREAS**, at the public hearing, the Planning Commission reviewed and considered the proposed amendments to the Marysville Municipal Code, and recommended that the City Council approve the proposed amendments to the Marysville Municipal Code.

**NOW, THEREFORE, THE CITY COUNCIL OF THE CITY OF MARYSVILLE, WASHINGTON, DO ORDAIN AS FOLLOWS:**

<sup>[BE2]</sup>

**Section 1. Required Findings.** In accordance with MMC 22G.010.520, the following findings are made regarding the proposed amendments to MMC sections 22C.020.060, 22C.020.070, and 22C.170.040<sup>[BE3]</sup> that are the subject of this ordinance:

- (1) The amendments are consistent with the purposes of the comprehensive plan;
- (2) The amendments are consistent with the purpose of Title 22 MMC;
- (3) There have been significant changes in the circumstances to warrant a change;
- (4) The benefit or cost to the public health, safety and welfare is sufficient to warrant the action.

**Section 2. Amendments to Development Regulations.** Section 22C.020.060, Section 22C.020.070, and Section 22C.170.040 of the Marysville Municipal Code are hereby amended as set forth in **Exhibit A**.

**Section 3. Severability.** If any section, subsection, sentence, clause, phrase, or word of this Ordinance should be held to be invalid or unconstitutional by a court of competent jurisdiction, such invalidity or unconstitutionality thereof shall not affect the validity or constitutionality of any other section, subsection, sentence, clause, phrase, or word of this Ordinance.

**Section 4. Correction.** Upon approval by the City Attorney, the City Clerk or the code reviser are authorized to make necessary corrections to this Ordinance, including

scrivener's errors or clerical mistakes; references to other local, state, or federal laws, rules, or regulations; or numbering or referencing of ordinances or their sections and subsections.

**Section 5. Effective Date.** This Ordinance shall become effective five days after the date of its publication by summary.

**PASSED AND APPROVED** by the Marysville City Council this 12th day of April, 2021.

CITY OF MARYSVILLE

\_\_\_\_\_  
Jon Nehring, Mayor

ATTEST:

By: \_\_\_\_\_  
City Clerk

APPROVED AS TO FORM:

By: \_\_\_\_\_  
Jon Walker, City Attorney

Date of Publication: \_\_\_\_\_

Effective Date: \_\_\_\_\_

## Exhibit A

### 22C.020.060 Permitted uses.

Specific Land Use	NB	CB	CB- WR	GC	DC	MU (63)	LI	GI	REC	P/I
<b>Residential Land Uses</b>										
<b>Dwelling Units, Types:</b>										
Townhouse					P6	P				
Multiple-family	C4	P4, C5		P4, C5	P4, P6	P				
Mobile home	P7	P7	P7	P7	P7	P7	P7	P7		
Senior citizen assisted	P					C				P
Caretaker's quarters (3)	P	P	P	P	P	P	P	P	P	P
<b>Group Residences:</b>										
Adult family home (70)	P	P	P	P	P	P				P
Convalescent, nursing, retirement	C	P			P	P				P
Residential care facility	P	P			P	P	P70	P70	P70	P
Master planned senior community (10)						C				C
<b><u>Enhanced Services Facility (77)</u></b>										
<b>Accessory Uses:</b>										
Home occupation (2)	P8	P8, P9	P8, P9	P8, P9	P8, P9	P8, P9	P9	P9		
<b>Temporary Lodging:</b>										
Hotel/motel	P	P	P	P	P	P	P75			
Bed and breakfast guesthouse (1)										
Bed and breakfast inn (1)	P	P	P	P						
<b>Recreation/Cultural Land Uses</b>										
<b>Park/Recreation:</b>										
Park	P11	P	P	P	P	P	P	P	P11	P
Marina					P			P	C	P
Dock and boathouse, private, noncommercial					P			P	P16	P
Recreational vehicle park				C12			C12		C	P
Boat launch, commercial or public					P			P		P
Boat launch, noncommercial or private					P			P	P17	P

Specific Land Use	NB	CB	CB-WR	GC	DC	MU (63)	LI	GI	REC	P/I
Community center	P	P	P	P	P	P	P	P	P	P
<b>Amusement/Entertainment:</b>										
Theater		P	P	P	P	P				
Theater, drive-in				C						
Amusement and recreation services		P18	P18	P18	P18	P19	P	C		
Sports club	P	P	P	P	P	P	P	P		
Golf facility (13)		P	P	P			P	P	C	
Shooting range (14)				P15			P15			
Outdoor performance center				C			C		C	C
Riding academy							P		C	
<b>Cultural:</b>										
Library, museum and art gallery	P	P	P	P	P	P	P	P	C	P
Church, synagogue and temple	P	P	P	P	P	P	P	P		P
Dancing, music and art center		P	P	P	P	P			C	P
<b>General Services Land Uses</b>										
<b>Personal Services:</b>										
General personal service	P	P	P	P	P	P	P	P		
Dry cleaning plant		P	P				P	P		
Dry cleaning pick-up station and retail service	P	P	P	P	P	P25	P76	P		
Funeral home/crematory		P	P	P	P	P26	P76	P		
Cemetery, columbarium or mausoleum	P24	P24	P24	P24, C20			P	P		
Day care I	P70	P70	P70	P70	P70	P70	P21, 70	P70	P70	P70
Day care II	P	P	P	P	P	P	P21			
Veterinary clinic	P	P	P	P	P	P	P76	P		
Automotive repair and service	P22	C, P28	C, P28	P			P	P		
Electric vehicle (EV) charging station (64)	P	P	P	P	P	P	P	P	P	P
EV rapid charging station (65), (66)	P	P	P	P	P67	P67	P	P		
EV battery exchange station				P			P	P		
Miscellaneous repair		P	P	P			P	P		
Social services		P	P	P	P	P				P
Kennel, commercial and exhibitor/breeding (71)		P	P	P			P	P		
Pet daycare (71), (72)		P	P	P	P	P	P76	P		

Specific Land Use	NB	CB	CB-WR	GC	DC	MU (63)	LI	GI	REC	P/I
Civic, social and fraternal association		P	P	P	P	C		P		P
Club (community, country, yacht, etc.)								P		P
<b>Health Services:</b>										
Medical/dental clinic	P	P	P	P	P	P				P
Hospital		P	P	P	P	C				C
Miscellaneous health	P68	P68	P68	P68	P68	P68				P68
Supervised drug consumption facility										
<b>Education Services:</b>										
Elementary, middle/junior high, and senior high (including public, private and parochial)		C	C	C	C	C	P	C		C
Commercial school	P	P	P		P	P27				C
School district support facility	C	P	P	P	P	P	P	P		P
Vocational school		P	P	P	P	P27				P
<b>Government/Business Service Land Uses</b>										
<b>Government Services:</b>										
Public agency office	P	P	P	P	P	P	P	P		P
Public utility yard				P			P			P
Public safety facilities, including police and fire	P29	P	P	P	P	P	P			P
Utility facility	P	P	P	P		C	P	P		P
Private storm water management facility	P	P	P	P	P	P	P	P		P
Public storm water management facility	P	P	P	P	P	P	P	P		P
<b>Business Services:</b>										
Contractors' office and storage yard				P30	P30	P30	P	P		
Interim recycling facility		P23	P23	P23			P			P
Taxi stands		P	P	P			P	P		
Trucking and courier service		P31	P31	P31			P	P		
Warehousing and wholesale trade				P			P	P		
Mini-storage (36)		<b>C 78</b>		<b>C 78</b>			P76	P		
Freight and cargo service				P			P	P		
Cold storage warehousing							P	P		
General business service and office	P	P	P	P	P	P30	P	P		
Commercial vehicle storage							P	P		
Professional office	P	P	P	P	P	P	P			
Miscellaneous equipment rental		P30, 37	P30, 37	C38		P30, 37	P	P		
Automotive rental and leasing				P			P	P		

Specific Land Use	NB	CB	CB-WR	GC	DC	MU (63)	LI	GI	REC	P/I
Automotive parking	P	P	P	P	P	P	P	P		
Research, development and testing				P			P	P		
Heavy equipment and truck repair							P	P		
Automobile holding yard				C			P	P		
Commercial/industrial accessory uses (73)	P39, 40	P39	P39	P39	P39, 40	P39, 40	P	P		
Adult facility								P33		
Factory-built commercial building (35)	P	P	P	P	P		P	P		
Wireless communication facility (32)	P, C	P, C	P, C	P, C	P, C	P, C	P, C	P, C		P, C
<b>State-Licensed Marijuana Facilities:</b>										
Marijuana cooperative (69)										
Marijuana processing facility – Indoor only (69)										
Marijuana production facility – Indoor only (69)										
Marijuana retail facility (69)										
<b>Retail/Wholesale Land Uses</b>										
Building, hardware and garden materials	P47	P	P	P	P	P47	P76	P		
Forest products sales		P	P	P			P			
Department and variety stores	P	P	P	P	P	P	P76			
Food stores	P	P	P	P	P	P45	P76			
Agricultural crop sales		P	P	P		C	P76			
Storage/retail sales, livestock feed							P76	P		
Motor vehicle and boat dealers		P	P	P			P	P		
Motorcycle dealers		C	C	P	P49		P	P		
Gasoline service stations	P	P	P	P	P		P76	P		
Eating and drinking places	P41	P	P	P	P	P46	P46	P		
Drug stores	P	P	P	P	P	P	P76	P		
Liquor stores		P	P	P						
Used goods: antiques/secondhand shops		P	P	P	P	P				
Sporting goods and related stores		P	P	P	P	P				
Book, stationery, video and art supply stores	P	P	P	P	P	P				
Jewelry stores		P	P	P	P	P				
Hobby, toy, game shops	P	P	P	P	P	P				
Photographic and electronic shops	P	P	P	P	P	P				
Fabric and craft shops	P	P	P	P	P	P				
Fuel dealers				P43			P43	P43		



Specific Land Use	NB	CB	CB-WR	GC	DC	MU (63)	LI	GI	REC	P/I
Florist shops	P	P	P	P	P	P				
Pet shops	P	P	P	P	P	P				
Tire stores		P	P	P	P		P76	P		
Bulk retail		P	P	P			P76			
Auction houses				P42			P76			
Truck and heavy equipment dealers							P	P		
Mobile home and RV dealers				C			P	P		
Retail stores similar to those otherwise named on this list	P	P	P	P	P	P48	P44, 76	P44		
Automobile wrecking yards							C	P		
<b>Manufacturing Land Uses</b>										
Food and kindred products		P50, 52	P50, 52	P50			P50	P		
Winery/brewery		P53	P53	P	P53	P53	P	P		
Textile mill products							P	P		
Apparel and other textile products				C			P	P		
Wood products, except furniture				P			P	P		
Furniture and fixtures				P			P	P		
Paper and allied products							P	P		
Printing and publishing	P51	P51	P51	P		P51	P	P		
Chemicals and allied products							C	C		
Petroleum refining and related industries							C	C		
Rubber and misc. plastics products							P	P		
Leather and leather goods							C	C		
Stone, clay, glass and concrete products							P	P		
Primary metal industries							C	P		
Fabricated metal products				C			P	P		
Industrial and commercial machinery							C	P		
Heavy machinery and equipment							C	P		
Computer and office equipment				C			P			
Electronic and other electric equipment				C			P			
Railroad equipment							C	P		
Miscellaneous light manufacturing				P54, 74	P54		P	P		
Motor vehicle and bicycle manufacturing							C	P		
Aircraft, ship and boat building							C	P		

Specific Land Use	NB	CB	CB-WR	GC	DC	MU (63)	LI	GI	REC	P/I
Tire retreading							C	P		
Movie production/distribution				P			P			
<b>Resource Land Uses</b>										
<b>Agriculture:</b>										
Growing and harvesting crops							P	P	P	
Raising livestock and small animals							P	P	P	
Greenhouse or nursery, wholesale and retail				P			P	P	C	
Farm product processing							P	P		
<b>Forestry:</b>										
Growing and harvesting forest products							P			
Forest research							P			
Wood waste recycling and storage							C	C		
<b>Fish and Wildlife Management:</b>										
Hatchery/fish preserve (55)							P	P	C	
Aquaculture (55)							P	P	C	
Wildlife shelters	C	C	C						P	
<b>Mineral:</b>										
Processing of minerals							P	P		
Asphalt paving mixtures and block							P	P		
<b>Regional Land Uses</b>										
Jail		C	C	C			C			
Regional storm water management facility		C	C	C	C		C	C		P
Public agency animal control facility				C			P	P		C
Public agency training facility		C56	C56	C56		C56	C57			C57
Nonhydroelectric generation facility	C	C	C	C			C	C		C
Energy resource recovery facility							C			
Soil recycling/incineration facility							C	C		
Solid waste recycling								C		C
Transfer station							C	C		C
Wastewater treatment facility							C	C		C
Transit bus base				C			P			C
Transit park and pool lot	P	P	P	P	P	P	P	P		P
Transit park and ride lot	P	P	P	P	P	P	P	P		C
School bus base	C	C	C	C			P			C58
Racetrack	C59	C59	C59	C			P			

Specific Land Use	NB	CB	CB-WR	GC	DC	MU (63)	LI	GI	REC	P/I
Fairground							P	P		C
Zoo/wildlife exhibit		C	C	C						C
Stadium/arena				C			C	P		C
College/university	C	P	P	P	P	P	P	P		C
Secure community transition facility								C60		
Opiate substitution treatment program facilities		P61, 62	P61, 62	P61, 62	P61, 62		P62	P62		

## 22C.020.070 Permitted uses – Development conditions.

(1) Bed and breakfast guesthouses and inns are subject to the requirements and standards contained in Chapter [22C.210](#) MMC, Bed and Breakfasts.

(2) Home occupations are subject to the requirements and standards contained in Chapter [22C.190](#) MMC, Home Occupations.

(3) Limited to one dwelling unit for the purposes of providing on-site service and security of a commercial or industrial business. Caretaker’s quarters are subject to the provisions set forth in Chapter [22C.110](#) MMC, entitled “Temporary Uses.”

(4) All units must be located above a street-level commercial use.

(5) Twenty percent of the units, but no more than two total units, may be located on the street level of a commercial use, if conditional use permit approval is obtained and the units are designed exclusively for ADA accessibility. The street-level units shall be designed so that the units are not located on the street front and primary access is towards the rear of the building.

(6) Permitted on the ground floor in the southwest sector of downtown vision plan area, as incorporated into the city of Marysville comprehensive plan.

(7) Mobile homes are only allowed in existing mobile home parks established prior to October 16, 2006.

(8) Home occupations are limited to home office uses in multifamily dwellings. No signage is permitted in townhouse or multifamily dwellings.

(9) Permitted in a legal nonconforming or conforming residential structure.

(10) Subject to Chapter [22C.220](#) MMC, Master Planned Senior Communities.

(11) The following conditions and limitations shall apply, where appropriate:

(a) Parks are permitted in residential and mixed use zones when reviewed as part of a subdivision or multiple-family development proposal; otherwise, a conditional use permit is required;

(b) Lighting for structures and fields shall be directed away from residential areas; and

(c) Structures or service yards shall maintain a minimum distance of 50 feet from property lines adjoining residential zones.

(12) Recreational vehicle parks are subject to the requirements and conditions of Chapter [22C.240](#) MMC.

(13) Golf Facility.

(a) Structures, driving ranges and lighted areas shall maintain a minimum distance of 50 feet from property lines adjoining residential zones.

(b) Restaurants are permitted as an accessory use to a golf course.

(14) Shooting Range.

(a) Structures and ranges shall maintain a minimum distance of 50 feet from property lines adjoining residential zones;

(b) Ranges shall be designed to prevent stray or ricocheting projectiles or pellets from leaving the property; and

(c) Site plans shall include safety features of the range; provisions for reducing noise produced on the firing line; and elevations of the range showing target area, backdrops or butts.

(15) Only in an enclosed building.

(16) Dock and Boathouse, Private, Noncommercial.

(a) The height of any covered over-water structure shall not exceed 20 feet as measured from the line of ordinary high water;

(b) The total roof area of covered, over-water structures shall not exceed 1,000 square feet;

(c) The entirety of such structures shall have not greater than 50 percent of the width of the lot at the natural shoreline upon which it is located;

(d) No over-water structure shall extend beyond the average length of all pre-existing over-water structures along the same shoreline and within 300 feet of the parcel on which proposed. Where no such pre-existing structures exist within 300 feet, the pier length shall not exceed 50 feet;

(e) Structures permitted hereunder shall not be used as a dwelling; and

(f) Covered structures are subject to a minimum setback of five feet from any side lot line or extension thereof. No setback from adjacent properties is required for any uncovered structure, and no setback from water is required for any structure permitted hereunder.

(17) Boat Launch, Noncommercial or Private.

(a) The city may regulate, among other factors, required launching depth, and length of docks and piers;

(b) Safety buoys shall be installed and maintained separating boating activities from other water-oriented recreation and uses where this is reasonably required for public safety, welfare and health; and

(c) All site improvements for boat launch facilities shall comply with all other requirements of the zone in which it is located.

(18) Excluding racetrack operation.

(19) Amusement and recreation services shall be a permitted use if they are located within an enclosed building, or a conditional use if located outside. In both instances they would be subject to the exclusion of a racetrack operation similar to other commercial zones.

(20) Structures shall maintain a minimum distance of 100 feet from property lines adjoining residential zones.

(21) Permitted as an accessory use; see MMC [22A.020.020](#), the definition of "Accessory use, commercial/industrial."

(22) Only as an accessory to a gasoline service station; see retail and wholesale permitted use table in MMC [22C.020.060](#).

(23) All processing and storage of material shall be within enclosed buildings and excluding yard waste processing.

(24) Limited to columbariums accessory to a church; provided, that existing required landscaping and parking are not reduced.

(25) Drive-through service windows in excess of one lane are prohibited in Planning Area 1.

(26) Limited to columbariums accessory to a church; provided, that existing required landscaping and parking are not reduced.

(27) All instruction must be within an enclosed structure.

(28) Car washes shall be permitted as an accessory use to a gasoline service station.

(29) Public Safety Facilities, Including Police and Fire.

(a) All buildings and structures shall maintain a minimum distance of 20 feet from property lines adjoining residential zones;

(b) Any buildings from which fire-fighting equipment emerges onto a street shall maintain a distance of 35 feet from such street.

(30) Outdoor storage of materials or vehicles must be accessory to the primary building area and located to the rear of buildings. Outdoor storage is subject to an approved landscape plan that provides for effective screening of storage, so that it is not visible from public right-of-way or neighboring properties.

(31) Limited to self-service household moving truck or trailer rental accessory to a gasoline service station.

(32) All WCFs and modifications to WCFs are subject to Chapter [22C.250](#) MMC including but not limited to the siting hierarchy, MMC [22C.250.060](#). WCFs may be a permitted use or a CUP may be required subject to MMC [22C.250.040](#).

(33) Subject to the conditions and requirements listed in Chapter [22C.030](#) MMC.

(34) Reserved.

(35) A factory-built commercial building may be used for commercial purposes subject to the following requirements:

(a) A factory-built commercial building must be inspected at least two times at the factory by the State Building and Electrical Inspector during the construction process, and must receive a state approval stamp certifying that it meets all requirements of the International Building and Electrical Codes. At the building site, the city building official will conduct foundation, plumbing and final inspections; and

(b) A factory-built commercial building cannot be attached to a metal frame allowing it to be mobile. All structures must be placed on a permanent, poured-in-place foundation. The foundation shall be structurally engineered to meet the requirements set forth in Chapter 16 of the International Building Code.

(36) Mini-storage facilities are subject to the development standards outlined in Chapter [22C.170](#) MMC.

(37) Except heavy equipment.

(38) With outdoor storage and heavy equipment.

(39) Incidental assembly shall be permitted; provided, it is limited to less than 20 percent of the square footage of the site excluding parking.

(40) Light industrial uses may be permitted; provided, there is no outdoor storage of materials, products or vehicles.

(41) Excluding drinking places such as taverns and bars and adult entertainment facilities.

- (42) Excluding vehicle and livestock auctions.
- (43) If the total storage capacity exceeds 6,000 gallons, a conditional use permit is required.
- (44) The retail sale of products manufactured on site shall be permitted; provided, that not more than 20 percent of the constructed floor area in any such development may be devoted to such retail use.
- (45) Limited to 5,000 square feet or less.
- (46) Eating and Drinking Places.
  - (a) Limited to 4,000 square feet or less.
  - (b) Drive-through service windows in excess of one lane are prohibited in Planning Area 1.
  - (c) Taverns, bars, lounges, etc., are required to obtain a conditional use permit in the mixed use zone.
- (47) Limited to hardware and garden supply stores.
- (48) Limited to convenience retail, such as video, and personal and household items.
- (49) Provided there is no outdoor storage and/or display of any materials, products or vehicles.
- (50) Except slaughterhouses.
- (51) Limited to photocopying and printing services offered to the general public.
- (52) Limited to less than 10 employees.
- (53) In conjunction with an eating and drinking establishment.
- (54) Provided there is no outdoor storage and/or display of any materials, products or vehicles.
- (55) May be further subject to the provisions of city of Marysville shoreline management program.
- (56) Except weapons armories and outdoor shooting ranges.
- (57) Except outdoor shooting ranges.
- (58) Only in conjunction with an existing or proposed school.
- (59) Except racing of motorized vehicles.
- (60) Limited to land located along east side of 47th Avenue NE alignment, in the east half of the northeast quarter of Section 33, Township 30N, Range 5E, W.M., and in the northeast quarter of the southeast quarter of Section 33, Township 30N, Range 5E, W.M., and land located east side of SR 529, north of Steamboat Slough, south and west of Ebey Slough (a.k.a. TP No. 300533-002-004-00)

and in the northwest and southwest quarters of Section 33, Township 30N, Range 5E, W.M., as identified in Exhibit A, attached to Ordinance No. 2452.

(61) Opiate substitution treatment program facilities permitted within commercial zones are subject to Chapter [22G.070](#) MMC, Siting Process for Essential Public Facilities.

(62) Opiate substitution treatment program facilities, as defined in MMC [22A.020.160](#), are subject to the standards set forth below:

(a) Shall not be established within 300 feet of an existing school, public playground, public park, residential housing area, child-care facility, or actual place of regular worship established prior to the proposed treatment facility.

(b) Hours of operation shall be restricted to no earlier than 6:00 a.m. and no later than 7:00 p.m. daily.

(c) The owners and operators of the facility shall be required to take positive ongoing measures to preclude loitering in the vicinity of the facility.

(63) Permitted uses include Whiskey Ridge zones.

(64) Level 1 and Level 2 charging only.

(65) The term “rapid” is used interchangeably with Level 3 and fast charging.

(66) Rapid (Level 3) charging stations are required to comply with the design and landscaping standards outlined in MMC [22C.020.265](#).

(67) Rapid (Level 3) charging stations are required to be placed within a parking garage.

(68) Excepting “marijuana (cannabis) dispensaries,” “marijuana (cannabis) collective gardens,” and “marijuana cooperatives” as those terms are defined or described in this code and/or under state law; such facilities and/or uses are prohibited in all zoning districts of the city of Marysville.

(69) No person or entity may produce, grow, manufacture, process, accept donations for, give away, or sell marijuana concentrates, marijuana-infused products, or usable marijuana within commercial, industrial, recreation, and public institution zones in the city. Provided, activities in strict compliance with RCW [69.51A.210](#) and [69.51A.260](#) are not a violation of the Marysville Municipal Code.

(70) Permitted within existing legal nonconforming single-family residences.

(71) Subject to the requirements set forth in MMC 10.04.460.\*

(72) Pet daycares are restricted to indoor facilities with limited, supervised access to an outdoor fenced yard. Overnight boarding may be permitted as a limited, incidental use. Both outdoor access and overnight boarding privileges may be revoked or modified if the facility is not able to comply with the noise standards set forth in WAC [173-60-040](#).\*



(73) Shipping/cargo and similar storage containers may be installed on commercial or industrial properties provided they are screened from public view pursuant to MMC [22C.120.160](#), Screening and impact abatement.

(74) Tanks, generators, and other machinery which does not generate nuisance noise may be located in the service/loading area. Truck service/loading areas shall not face the public street and shall be screened from the public street.

(75) Hotels/motels are prohibited within Arlington Airport Inner Safety Zones (ISZ) 2, 3, and 4. Hotel/motels that are proposed to locate within Arlington Airport Protection Subdistricts B and C shall be required to coordinate with the Arlington Municipal Airport to ensure that height, glare, and other aspects of the hotels/motels are compatible with air traffic and airport operations.

(76) Use limited to properties that have property frontage along State Avenue/Smokey Point Boulevard.

(77) Enhanced Services Facilities are prohibited in all commercial and industrial zones as such are identified and adopted in chapter 22C.020 MMC.

(78) Mini-storage facilities may be allowed in the CB and GC zone as a conditional use on property located east of Interstate 5, North of 100<sup>th</sup> Street, and west of 47th Avenue NE, subject to the following conditions:

1. The property does not have direct frontage on an arterial street.
2. Vehicular access to the property is limited by physical constraints, such as railroad tracks, proximity to congested public street intersection where turning movements are restricted, or other physical barriers that limit convenient vehicular access for higher traffic-generating uses such as retail or office.
3. Buildings shall be located a minimum of 150 feet from the nearest arterial street or interstate highway right-of-way.

## **22C.170.040 Design considerations.**

The following exterior design requirements apply to ~~a mini-storage facilities facility when located adjacent to or across a right-of-way from a residentially zoned or designated property.~~

(1) Architectural Features. Architectural features are to be consistent with the character of the surrounding neighborhood. The following are minimum standards.

(a) Minimum roof pitch is 4:12 for buildings with less than three floors.

(b) Exterior vertical surfaces require 50 percent of the area to be materials such as decorative brick veneer, stone, stucco, textured block, and other materials which reflect residential design elements.

(c) Unique architectural features such as towers, turrets and pergolas are subject to the standards of this subsection. An applicant is required to demonstrate that the proposed architectural features are consistent with the neighborhood character.

(d) Access points, except for emergency access, may not be from a local access street; provided that when a conditional use permit is required, the City may allow access from a local street if it determines traffic will not be disruptive to residential uses.

(e) Fencing is required to be low-maintenance material and articulation at intervals no greater than 20 feet. Chain-link fencing is not permitted.

(f) Display and floodlighting is required to be constructed, shielded and used so as not to directly illuminate, or create glare visible from, adjacent property or public right-of-way.

(g) A building or series of buildings parallel with and adjacent to residentially zoned or developed property or street frontage must have staggered setbacks for every ~~400~~ 50 feet of lineal development. The setbacks shall be stepped back or projected forward at intervals to provide a minimum of 40 percent facade modulation. The minimum depth of modulation should be ~~one~~ four feet ~~feet~~, and the minimum width should be ~~five~~ eight feet. There must be at least 10 feet of separation between buildings.

(h) Where allowed as a conditional use in the CB and GC zones, the following regulations shall apply:

(i) Outdoor storage of trucks, boats, recreational vehicles or other types of vehicles or equipment is permitted subject to the following standards:

(A) outdoor storage areas are not visible from abutting properties or public right-of-way through the use of buildings, or other method of solid screening; and

(B) the area devoted to outdoor storage is less than fifty percent of the footprint of the storage building(s).

(ii) Buildings shall have a minimum height of three floors, except in the following circumstances:

(A) When there is more than one building, only buildings located within fifty feet of a public street shall have a height of three floors; or

(B) The City may allow less than three floors if the applicant proposes an architectural and landscape design quality that is superior to what is otherwise required by development standards and design guidelines applicable to a building containing three floors. To determine if the quality is superior, the scale and design of the building, exterior building materials and landscaping treatment proposed must be comparable to what would be required for a retail or office building. The City shall take into consideration compatibility of the proposed design with existing development, or the likely future development, of surrounding properties.

(2) Landscaping and Screening. The following landscaping and screening requirements apply to all mini-storage facilities:

(a) All setback areas shall be landscaped with a variety of trees, shrubs and ground cover plants consistent with L2 landscaping as defined under Chapter [22C.120](#) MMC, Landscaping and Screening.

(b) A solid wall, a screening fence or a combination of both achieving a perimeter screening to a minimum of six feet in height is required and shall be located so that a minimum of 75 percent of the landscaping area is outside the fence.

~~(c) All use of the site shall comply with the city noise standards stated in Chapter [6.76](#) MMC. (Ord. 2852 § 10 (Exh. A), 2011).~~

DRAFT