

CITY OF MARYSVILLE AGENDA BILL
EXECUTIVE SUMMARY FOR ACTION

CITY COUNCIL MEETING DATE: May 3, 2021 Briefing; May 10, 2021 Action

AGENDA ITEM:	
Ordinance amending the Unified Development Code to amend the definition of “enhanced services facilities;” allow “enhanced services facilities” as a Conditional Use in the R-18 and R-28 zones, and as a permitted use in the CB Community Business, CB-WR Community Business Whiskey Ridge, DC Downtown Commercial, GC General Commercial, and MU Mixed Use zones; and adding a new chapter 22C.280 MMC concerning “enhanced services facilities;” and repealing Ordinance No. 3168.	
PREPARED BY:	DIRECTOR APPROVAL:
Allan Giffen, Community Development staff	<i>Jaylie Miller</i> , CD Director
DEPARTMENT:	
Community Development	
ATTACHMENTS:	
Ordinance	
BUDGET CODE:	AMOUNT:
N/A	N/A
SUMMARY:	

The City Council adopted an Ordinance No. 3168 on November 23, 2020, establishing an interim regulation that prohibits the siting of Enhanced Services Facilities (ESFs) in Marysville while the City studies where such uses may be allowed. The Planning Commission held public meetings to discuss the matter on December 8, 2020, January 12, 2021 and February 9, 2021. On February 23, 2021, the Planning Commission held a public hearing and recommended amendments to the Marysville Municipal Code contained in the attached ordinance. The proposed changes:

- Amend the definition of “enhanced services facilities” to match the State definition
- Allow ESFs as a conditional use in the R-18 and R-28 multi-family zones
- Allow ESFs as a permitted use in the CB, CB-WR, DC, GC and MU commercial zones
- Establish a new chapter in the MMC with additional regulations for ESFs

RECOMMENDED ACTION:

Staff recommends that Council approve Ordinance No. ____, amending the Marysville Municipal Code Title 22C concerning Enhanced Services Facilities, and repealing Ordinance No. 3168.

RECOMMENDED MOTION:

I move to approve Ordinance No. ____, amending the Marysville Municipal Code Title 22C concerning Enhanced Services Facilities, and repealing Ordinance No. 3168.

**CITY OF MARYSVILLE
WASHINGTON**

ORDINANCE NO. _____

AN ORDINANCE OF THE CITY OF MARYSVILLE, WASHINGTON, UPDATING TITLE 22C OF THE MARYSVILLE MUNICIPAL CODE; AMENDING THE DEFINITION OF “ENHANCED SERVICES FACILITIES; ALLOWING “ENHANCED SERVICES FACILITIES” AS A CONDITIONAL USE IN THE R-18 MEDIUM DENSITY MULTI-FAMILY AND R-28 HIGH DENSITY MULTI-FAMILY ZONES; AND AS A PERMITTED USE IN THE CB COMMUNITY BUSINESS, CB-WR COMMUNITY BUSINESS-WHISKEY RIDGE, DC DOWNTOWN COMMERCIAL, GC GENERAL COMMERCIAL, AND MU MIXED USE ZONES; AMENDING MMC 22A.020.060, “E” DEFINITIONS; AMENDING MMC 22C.010.060 AND 22C.020.060, PERMITTED USES; AMENDING MMC 22C.010.070 AND 22C.020.070, PERMITTED USES – DEVELOPMENT CONDITIONS; AND ESTABLISHING A NEW CHAPTER 22C.280 CONCERNING ENHANCED SERVICES FACILITIES; AND REPEALING ORDINANCE NO. 3168.

WHEREAS, the State Growth Management Act, Chapter 36.70A RCW mandates that cities periodically review and amend development regulations, including zoning ordinances and official controls; and

WHEREAS, RCW 36.70A.106 requires the processing of amendments to the City's development regulations in the same manner as the original adoption of the City's comprehensive plan and development regulations; and

WHEREAS, the State Growth Management Act requires notice and broad public participation when adopting or amending the City's comprehensive plan and development regulations; and

WHEREAS, the City, in reviewing and amending its development regulations has complied with the notice, public participation, and processing requirements established by the Growth Management Act, as more fully described below; and

WHEREAS, the City Council of the City of Marysville finds that from time to time it is necessary and appropriate to review and revise provisions of the City's municipal code and development code (MMC Title 22); and

WHEREAS, the Marysville City Council adopted Ordinance No. 3168 on November 23, 2020, which adopted an interim development regulation establishing a definition for “Enhanced services facilities” and specifying that “Enhanced services facilities” are not a permitted use in any zone in the City of Marysville; and

WHEREAS, the Marysville City Council adopted Ordinance No. 3168 as an Emergency Ordinance which provided that the interim development regulation is effective for six months from the effective date of the ordinance (November 23, 2020); and

WHEREAS, the proposed amendments were submitted to the State of Washington Department of Commerce for 60-day review on February 1, 2021, in accordance with RCW 36.70A.106; and

WHEREAS, the Planning Commission held public work sessions on December 8, 2020, January 12, 2021, and February 9, 2021, to review the proposed amendments, including alternatives, and did hear and consider public comments; and

WHEREAS, the Planning Commission held a duly-advertised public hearing on February 23, 2021, and received testimony from City staff and the public; and

WHEREAS, at the public hearing, the Planning Commission reviewed and considered the proposed amendments to the Marysville Municipal Code, and recommended that the City Council approve the proposed amendments to the Marysville Municipal Code; and

WHEREAS, the proposed amendments to Title 22 of the Marysville Municipal Code (comprising of **(a)** proposed amendments to MMC Sections 22A.020.060, 22C.010.060; 22C.020.060, 22C.010.070, 22C.020.070, and **(b)** a new proposed new Chapter 22C.280 MMC), were reviewed under the State Environmental Policy Act; which review resulted in the issuance of a Determination of Non-Significance (DNS) on April 5, 2021.

NOW, THEREFORE, THE CITY COUNCIL OF THE CITY OF MARYSVILLE, WASHINGTON, DO ORDAIN AS FOLLOWS:

Section 1. Required Findings. In accordance with MMC 22G.010.520, the following findings are made regarding the proposed amendments to Title 22 of the Marysville Municipal code (comprising of **(a)** proposed amendments to MMC Sections 22A.020.060, 22C.010.060, 22C.020.060, 22C.010.070, and 22C.020.070, and **(b)** a proposed new Chapter 22C.280 MMC) that are the subject of this ordinance:

- (1) The amendments are consistent with the purposes of the comprehensive plan;
- (2) The amendments are consistent with the purpose of Title 22 MMC;
- (3) There have been significant changes in the circumstances to warrant a change;
- (4) The benefit or cost to the public health, safety and welfare is sufficient to warrant the action.

Section 2. Amendment to Development Regulations: Modification of Current Code Sections. Sections 22A.020.060, 22C.010.060; 22C.020.060, 22C.010.070, and 22C.020.070 of the Marysville Municipal Code are hereby amended as set forth in **Exhibit A.**

Section 3. Amendment to Development Regulations: Adoption of Chapter 22C.280 MMC. A new Chapter 22C.280 of the Marysville Municipal Code is adopted as set forth in **Exhibit B.**

Section 4. Repeal of Ordinance No. 3168. Ordinance No. 3168 shall be repealed upon the effective date of this Ordinance.

Section 5. Severability. If any section, subsection, sentence, clause, phrase, or word of this Ordinance should be held to be invalid or unconstitutional by a court of competent jurisdiction, such invalidity or unconstitutionality thereof shall not affect the validity or constitutionality of any other section, subsection, sentence, clause, phrase, or word of this Ordinance.

Section 6. Correction. Upon approval by the City Attorney, the City Clerk or the code reviser are authorized to make necessary corrections to this Ordinance, including scrivener's errors or clerical mistakes; references to other local, state, or federal laws, rules, or regulations; or numbering or referencing of ordinances or their sections and subsections.

Section 7. Effective Date. This Ordinance shall become effective five days after the date of its publication by summary.

PASSED AND APPROVED by the Marysville City Council this 10th day of May, 2021.

CITY OF MARYSVILLE

Jon Nehring, Mayor

ATTEST:

By: _____
City Clerk

APPROVED AS TO FORM:

By: _____
Jon Walker, City Attorney

Date of Publication: _____

Effective Date: _____

EXHIBIT A

22A.020.060 “E” definitions.

“Easement” means a right granted by a property owner to specifically named parties or to the public for the use of certain land for specified purposes.

“Effective date” means the date a final decision becomes effective.

“EIS” means environmental impact statement.

“Elderly” means a person 62 years of age or older.

“Electric scooters and motorcycles” means any two-wheel vehicle that operates exclusively on electrical energy from an off-board source that is stored in the vehicle’s batteries and produces zero emissions or pollution when stationary or operating.

“Electric sign” means any sign containing electrical wiring, lighting, or other electrical components, but not including signs illuminated by a detached exterior light source.

“Electric vehicle” means any vehicle that operates, either partially or exclusively, on electrical energy from the grid, or an off-board source, that is stored on board for motive purpose. “Electric vehicle” includes:

- (1) A battery electric vehicle;
- (2) A plug-in hybrid electric vehicle;
- (3) A neighborhood electric vehicle; and
- (4) A medium-speed electric vehicle.

“Electric vehicle charging station” means a public or private parking space that is served by battery charging station equipment that has as its primary purpose the transfer of electric energy (by conductive or inductive means) to a battery or other energy storage device in an electric vehicle. An electric vehicle charging station equipped with Level 1 or Level 2 charging equipment is permitted outright as an accessory use to any principal use.

“Electric vehicle charging station – public” means an electric vehicle charging station that is:

- (1) Publicly owned and publicly available (e.g., park and ride parking, public library parking lot, on-street parking); or
- (2) Privately owned and publicly available (e.g., shopping center parking, nonreserved parking in multifamily parking lots).

“Electric vehicle charging station – restricted” means an electric vehicle charging station that is:

(1) Privately owned and restricted access (e.g., single-family home, executive parking, designated employee parking); or

(2) Publicly owned and restricted (e.g., fleet parking with no access to the general public).

“Electric vehicle infrastructure” means structures, machinery, and equipment necessary and integral to support an electric vehicle, including battery charging stations, rapid charging stations, and battery exchange stations.

“Electric vehicle parking space” means any marked parking space that identifies the use to be exclusively for the parking of an electric vehicle.

“Electronic message sign” means a variable message sign that utilizes computer-generated messages or some other electronic means of changing copy. These signs include displays using incandescent lamps, LEDs, LCDs or a flipper matrix. Also known as “changeable copy sign.”

“Elevated building (floodplain management)” means, for insurance purposes, a nonbasement building which has its lowest elevated floor raised above ground level by foundation walls, shear walls, posts, piers, pilings, or columns.

“Elevation certificate” means an administrative tool of the National Flood Insurance Program (NFIP) that can be used to provide elevation information, to determine the proper insurance premium rate, and to support a request for a letter of map amendment (LOMA) or letter of map revision based on fill (LOMR-F).

“Eligible facilities request” means any request for modification of an existing tower or base station that does not substantially change the physical dimensions of such tower or base station, involving:

(1) Co-location of new transmission equipment;

(2) Removal of transmission equipment; or

(3) Replacement of transmission equipment.

Criteria on what constitutes a substantial change is set forth in MMC [22C.250.210](#).

“Eligible support structure” means any existing tower or base station as defined in Chapter [22C.250](#) MMC; provided, that it is existing at the time an eligible facilities modification application is filed with the city.

“Emergency notification services” means services that notify the public of an emergency.

“Emergency services” means 911 emergency services and emergency notification services.

“Emergency support services” means information or database management services used in support of emergency services.

“Energy resource recovery facility” means an establishment for recovery of energy in a usable form from mass burning or refuse-derived fuel incineration, pyrolysis or any other means of using the heat of combustion of solid waste.

“Engineering feasibility study” means a report prepared by a licensed professional engineer qualified by training to have expert engineering knowledge of a particular subject. The report will identify the capability of the land to withstand disturbance, such as erosion, sedimentation, geological hazards, or other aspects of the development.

"Enhanced services facility" means a facility that provides support and services to persons for whom acute inpatient treatment is not medically necessary.

~~"Enhanced services facility" means a facility that provides support and services to persons for whom acute inpatient treatment is not medically necessary and which typically serves individuals with either a mental disorder, a substance use disorder, or co-occurring mental disorder and substance use disorder. Such facilities shall be limited to a maximum 16-bed capacity and shall meet all of the regulatory and licensing requirements of the state of Washington per Chapter 70.97 RCW.~~

“Environmentally sensitive areas” means those areas regulated by Chapter [22E.010](#) MMC, and their buffers.

“Equipment, heavy” means high-capacity mechanical devices for moving earth or other materials, and mobile power units including, but not limited to:

- (1) Carryalls;
- (2) Graders;
- (3) Loading and unloading devices;
- (4) Cranes;
- (5) Drag lines;
- (6) Trench diggers;
- (7) Tractors;
- (8) Augers;
- (9) Bulldozers;
- (10) Concrete mixers and conveyers;
- (11) Harvesters;
- (12) Combines; or

(13) Other major agricultural equipment and similar devices operated by mechanical power as distinguished from manpower.

“Erosion” means the wearing away of the earth’s surface as a result of the movement of wind, rain, water and other natural agents which mobilize and transport soil particles.

“Erosion hazard areas” means lands or areas that, based on a combination of slope inclination and the characteristics of the underlying soils, are susceptible to varying degrees of risk of erosion. Erosion hazard areas are classified as low hazard, moderate hazard and high hazard, based on the following criteria:

(1) Low Hazard. Areas sloping less than 15 percent.

(2) Moderate Hazard. Areas sloping between 15 and 40 percent and underlain by soils that consist predominantly of silt, clay, bedrock or glacial till.

(3) High Hazard. Areas sloping between 15 and 40 percent that are underlain by soils consisting largely of sand and gravel, and all areas sloping more steeply than 40 percent.

“Evergreen” means a plant species with foliage that persists and remains green year-round.

“Ex parte communication” means any oral or written communication made by any person, including a city employee or official, pertaining to a matter that is or will be within the jurisdiction of the city council, hearing examiner or planning commission made outside of a public record.

Exceptions (Shoreline Master Program) – Requirements to Obtain Shoreline Permits or Local Reviews (Shoreline Master Program). Requirements to obtain a substantial development permit, conditional use permit, variance, letter of exemption, or other review to implement the shoreline management act do not apply to the following:

(1) Remedial Actions. Pursuant to RCW [90.58.355](#), any person conducting a remedial action at a facility pursuant to a consent decree, order, or agreed order pursuant to Chapter [70.105D](#) RCW, or to the Department of Ecology when it conducts remedial action under Chapter [70.105D](#) RCW.

(2) Boat Yard Improvements to Meet NPDES Permit Requirements. Pursuant to RCW [90.58.355](#), any person installing site improvements for storm water treatment in an existing boatyard facility to meet requirements of a National Pollutant Discharge Elimination System storm water general permit.

(3) WSDOT Facility Maintenance and Safety Improvements. Pursuant to RCW [90.58.356](#), Washington State Department of Transportation projects and activities meeting the conditions of RCW [90.58.356](#) are not required to obtain a substantial development permit, conditional use permit, variance, letter of exemption, or other local review.

(4) Projects consistent with an environmental excellence program agreement pursuant to RCW [90.58.045](#).

(5) Projects authorized through the Energy Facility Site Evaluation Council process, pursuant to Chapter [80.50](#) RCW.

Exemption (Shoreline Master Program). Certain specific developments as listed in WAC [173-27-040](#) as exempt from the definition of “substantial developments” are therefore exempt from the substantial development permit process of the SMA. An activity that is exempt from the substantial development provisions of the SMA must still be carried out in compliance with policies and standards of the Act and the local master program. Conditional use and/or variance permits may also still be required even though the activity does not need a substantial development permit. (RCW [90.58.030](#)(3)(e); WAC [173-27-040](#).) “Exemption (shoreline master program)” also includes the external retrofitting of an existing structure with the exclusive purpose of compliance with the Americans with Disabilities Act of 1990 (42 USC Sec. 12010 et seq.) or to otherwise provide physical access to the structure by individuals with disabilities.

“Existing and ongoing agricultural activities (small farms overlay zone)” means those activities involved in the production of crops and livestock, and changes between agricultural activities and uses, and normal operation, maintenance, repair, or reconstruction of existing serviceable structures, as well as construction of new farm structures, facilities or improved areas. An operation ceases to be ongoing when a formal plat has been approved by the city for development of the small farm.

“Existing and ongoing agricultural activities” means those activities involved in the production of crops and livestock, including but not limited to operation and maintenance of farm and stock ponds or drainage and irrigation systems, changes between agricultural activities and uses, and normal operation, maintenance, repair, or reconstruction of existing serviceable structures, facilities or improved areas. Activities which bring an area into agricultural use are not part of an ongoing activity. An operation ceases to be ongoing when the area on which it was conducted is proposed for conversion to a nonagricultural use or has lain idle for a period of longer than five years, unless the idle land is registered in a federal or state soils conservation program. Forest practices are not included in this definition.

“Existing manufactured home park or subdivision (floodplain management)” means a manufactured home park or subdivision for which the construction of facilities for servicing the lots on which the manufactured homes are to be affixed (including, at a minimum, the installation of utilities, the construction of streets, and either final site grading or the pouring of concrete pads) is completed before the effective date of the adopted floodplain management regulations.

“Existing (wireless communication facilities)” for purposes of Chapter [22C.250](#) MMC where it is related to a constructed tower or base station, means a constructed tower or base station that has been reviewed and approved under the applicable zoning or siting process or under another applicable state or local regulatory review process, and the term also includes a tower that was lawfully constructed but that was not reviewed and approved because it was not in a zoned area when it was built.

“Exotic species” means any species of plant or animal that is not indigenous to the area.

“Expansion to an existing manufactured home park or subdivision (floodplain management)” means the preparation of additional sites by the construction of facilities for servicing the lots on which the manufactured homes are to be affixed (including the installation of utilities, the construction of streets, and either final site grading or the pouring of concrete pads). (Ord. 3168 § 2 (Exh. A), 2020*; Ord. 3151 § 5, 2020; Ord. 3146 § 6, 2020; Ord. 3125 § 3 (Exh. B), 2019; Ord. 2852 § 10 (Exh. A), 2011).

* ~~Code reviser's note: Ord. 3168 Section 3 states: "This interim development regulation shall be in effect for six (6) months following the effective date of this Ordinance" and shall expire June 2, 2021.~~

2C.010.060 Permitted uses.

Specific Land Use	R-4.5	R-6.5	R-8	WR R-4-8	R-12	R-18	R-28	WR R-6- 18	R- MHP
Residential Land Uses									
Dwelling Units, Types:									
Single detached (14)	P11	P11	P11	P11	P11	P11	P11	P11	P43
Model home	P30	P30	P30	P30	P30	P30	P30	P30	P30
Cottage housing (14)	C6	C6	C6	C6	C6	C6	C6	C6	
Duplex (14)	C8	P8	P8	P8	P	P	P	P	
Townhouse	P3	P3	P3	P3	P	P	P	P	
Multiple-family					P	P	P	P	
Mobile home	P12	P12	P12	P12	P12	P12	P12	P12	P12
Mobile/manufactured home park	P3	P3	P3		C	P	P		P45
Senior citizen assisted	C2	C2	C2	C2	C2	C2	C2	C2	C2
Factory-built	P7	P7	P7	P7	P7	P7	P7	P7	P7, 43
Recreational vehicle (44)	P	P	P	P	P	P	P	P	P
Tiny house or tiny house with wheels (51)	P	P	P	P	P	P	P	P	P
Group Residences:									
Adult family home	P	P	P	P	P	P	P	P	P
Convalescent, nursing, retirement	C2	C2	C2	C2	C2	C2	C2	C2	
Residential care facility	P	P	P	P	P	P	P	P	
Master planned senior community (15)	C	C	C	C	C	C	C	C	C
Accessory Uses:									
Residential accessory uses (1), (9), (10), (14), (49), (50)	P	P	P	P	P	P	P	P	P
Home occupation (5)	P	P	P	P	P13	P13	P13	P13	P
Temporary Lodging:									
Hotel/motel					P	P	P	P	
Bed and breakfast guesthouse (4)		C	C	C	P	P	P	P	
Bed and breakfast inn (4)					P	P	P	P	
Enhanced services facility (52)						<u>C</u>	<u>C</u>		

Specific Land Use	R-4.5	R-6.5	R-8	WR R-4-8	R-12	R-18	R-28	WR R-6- 18	R- MHP
Recreation/Cultural Land Uses									
Park/Recreation:									
Park	P16	P16	P16	P16	P16	P16	P16	P16	P16
Community center	C	C	C	C	C	C	C	C	C
Amusement/Entertainment:									
Sports club					C	C	C	C	
Golf facility (17)	C	C	C	C	P	P	P	P	
Cultural:									
Library, museum and art gallery	C	C	C	C	C	C	C	C	C
Church, synagogue and temple	C	C	C	C	P	P	P	P	C
General Services Land Uses									
Personal Services:									
Funeral home/crematory	C18	C18	C18	C18	C18	C18	C18	C18	C18
Cemetery, columbarium or mausoleum	P24 C19	P24 C19	P24 C19	P24 C19	P24 C19	P24 C19	P24 C19	P24 C19	P24 C19
Day care I	P20	P20	P20	P20	P20	P20	P20	P20	P20
Day care II	C25	C25	C25	C25	C	C	C	C	C25
Stable	C	C	C	C					
Kennel or cattery, hobby	C	C	C	C	C	C	C	C	
Electric vehicle (EV) charging station (38), (39)	P	P	P	P	P	P	P	P	
EV rapid charging station (40), (41), (42)					P	P	P	P	
Health Services:									
Medical/dental clinic					C	C	C	C	
Supervised drug consumption facility									
Education Services:									
Elementary, middle/junior high, and senior high (including public, private and parochial)	C	C	C	C	C	C	C	C	C
Commercial school	C21	C21	C21	C21	C21	C21	C21	C21	
School district support facility	C23	C23	C23	C23	C23	C23	C23	C23	
Interim recycling facility	P22	P22	P22	P22	P22	P22	P22	P22	
Vocational school									
Government/Business Service Land Uses									
Government Services:									
Public safety facilities, including police and fire	C26	C26	C26	C26	C26	C26	C26	C26	C26
Utility facility	P	P	P	P	P	P	P	P	P

Specific Land Use	R-4.5	R-6.5	R-8	WR R-4-8	R-12	R-18	R-28	WR R-6- 18	R- MHP
Private storm water management facility	P	P	P	P	P	P	P	P	P
Public storm water management facility	P	P	P	P	P	P	P	P	P
Business Services:									
Self-service storage (31)					C27	C27	C27	C27	
Professional office					C	C	C	C	
Automotive parking	P29	P29	P29	P29	P29	P29	P29	P29	
Model house sales office	P47	P47	P47	P47					
Wireless communication facility (28)	P C	P C	P C	P C	P C	P C	P C	P C	P C
State-Licensed Marijuana Facilities:									
Marijuana cooperative (48)									
Marijuana processing facility – Indoor only (48)									
Marijuana production facility – Indoor only (48)									
Marijuana retail facility (48)									
Retail/Wholesale Land Uses									
Forest products sales	P32	P32	P32	P32					
Agricultural crop sales	P32	P32	P32	P32					
Resource Land Uses									
Agriculture:									
Growing and harvesting crops	P34	P34	P34	P34					
Raising livestock and small animals	P35	P35	P35	P35					
Forestry:									
Growing and harvesting forest products	P34	P34	P34	P34					
Fish and Wildlife Management:									
Hatchery/fish preserve (33)	C	C	C	C					
Aquaculture (33)	C	C	C	C					
Regional Land Uses									
Regional storm water management facility	C	C	C	C	C	C	C	C	C
Nonhydroelectric generation facility	C	C	C	C	C	C	C	C	C
Transit park and pool lot	P	P	P	P	P	P	P	P	
Transit park and ride lot	C	C	C	C	C	C	C	C	
School bus base	C36	C36	C36	C36	C36	C36	C36	C36	
Racetrack	C37	C37	C37	C37	C37	C37	C37	C37	
College/university	C	C	C	C	C	C	C	C	

22C.010.070 Permitted uses – Development conditions.

- (1) Accessory dwelling units must comply with development standards in Chapter [22C.180](#) MMC. Accessory dwelling units in the MHP zone are only allowed on single lots of record containing one single-family detached dwelling.
- (2) Limited to three residents per the equivalent of each minimum lot size or dwelling units per acre allowed in the zone in which it is located.
- (3) Only as part of a planned residential development (PRD) proposal, and subject to the same density as the underlying zone.
- (4) Bed and breakfast guesthouses and inns are subject to the requirements and standards contained in Chapter [22C.210](#) MMC.
- (5) Home occupations are subject to the requirements and standards contained in Chapter [22C.190](#) MMC.
- (6) Subject to cottage housing provisions set forth in MMC [22C.010.280](#).
- (7) Factory-built dwelling units shall comply with the following standards:
 - (a) A factory-built house must be inspected at least two times at the factory by the State Building Inspector during the construction process, and must receive an approval certifying that it meets all requirements of the International Building Code. At the building site, the city building official will conduct foundation, plumbing and final inspections.
 - (b) A factory-built house cannot be attached to a metal frame allowing it to be mobile. All such structures must be placed on a permanent foundation at the building site.
- (8) Permitted outright in the R-6.5, R-8, and WR-R-4-8 zones on minimum 7,200-square-foot lots. A conditional use permit is required for the R-4.5 zone, and the minimum lot size must be 12,500 square feet. Duplexes must comply with the comprehensive plan density requirements for the underlying land use designation.
- (9) A garage sale shall comply with the following standards:
 - (a) No residential premises shall have more than two such sales per year and no such sale shall continue for more than six days within a 15-day period.
 - (b) Signs advertising such sales shall not be attached to any public structures, signs or traffic control devices, nor to any utility poles. All such signs shall be removed 24 hours after the sale is completed.

A garage sale complying with the above conditions shall be considered as being an allowable accessory use to all residential land uses. A garage sale violating one or more of the above conditions shall be considered as being a commercial use and will be disallowed unless it complies with all requirements affecting commercial uses.

(10) Residential accessory structures must comply with development standards in Chapter [22C.180](#) MMC.

(11) Manufactured homes must:

(a) Be set on a permanent foundation, as specified by the manufacturer, enclosed with an approved concrete product from the bottom of the home to the ground which may be either load-bearing or decorative;

(b) Meet all design standards applicable to all other single-family homes in the neighborhood in which the manufactured home is to be located;

(c) Be no more than five years old, as evidenced by the date of manufacture recorded on the HUD data plate. An administrative variance to the requirement that a manufactured home be no more than five years old may be granted by the community development director only if the applicant demonstrates all of the following:

(i) The strict enforcement of the provisions of this title creates an unnecessary hardship to the property owner;

(ii) The proposed manufactured home is well maintained and does not present any health or safety hazards;

(iii) The variance is necessary or warranted because of the unique size, shape, topography, location, critical areas encumbrance, or other feature of the subject property;

(iv) The proposed manufactured home will be compatible with the neighborhood or area where it will be located;

(v) The subject property is otherwise deprived, by provisions of this title, of rights and privileges enjoyed by other properties in the vicinity and within an identical zone;

(vi) The need for the variance is not the result of deliberate actions of the applicant or property owner; and

(vii) The variance is the minimum necessary to grant relief to the applicant.

(12) Mobile homes are only allowed as a primary residence in existing mobile/manufactured home parks established prior to June 12, 2008, subject to the requirements of Chapter [22C.230](#) MMC, Mobile/Manufactured Home Parks.

(13) Home occupations are limited to home office uses in multifamily dwellings. No signage is permitted in townhouse or multifamily dwellings.

(14) No more than one single-family detached or duplex dwelling is allowed per lot except in cottage housing developments that are developed with all cottages located on a common lot, and accessory dwelling units through the provisions of Chapter [22C.180](#) MMC.

(15) Subject to Chapter [22C.220](#) MMC, Master Planned Senior Communities.

(16) The following conditions and limitations shall apply, where appropriate:

(a) Parks are permitted in residential and mixed use zones when reviewed as part of a subdivision, mobile/manufactured home park, or multiple-family development proposal; otherwise, a conditional use permit is required;

(b) Lighting for structures and fields shall be directed away from residential areas; and

(c) Structures or service yards shall maintain a minimum distance of 50 feet from property lines adjoining residential zones.

(17) Golf facilities shall comply with the following:

(a) Structures, driving ranges and lighted areas shall maintain a minimum distance of 50 feet from property lines adjoining residential zones.

(b) Restaurants are permitted as an accessory use to a golf course.

(18) Only as an accessory to a cemetery.

(19) Structures shall maintain a minimum distance of 100 feet from property lines adjoining residential zones.

(20) Only as an accessory to residential use and subject to the criteria set forth in Chapter [22C.200](#) MMC.

(21) Only as an accessory to residential use, provided:

(a) Students are limited to 12 per one-hour session;

(b) All instruction must be within an enclosed structure; and

(c) Structures used for the school shall maintain a distance of 25 feet from property lines adjoining residential zones.

(22) Limited to drop box facilities accessory to a public or community use such as a school, fire station or community center.

(23) Only when adjacent to an existing or proposed school.

(24) Limited to columbariums accessory to a church; provided, that existing required landscaping and parking are not reduced.

(25) Day care IIs must be located on sites larger than one-half acre and are subject to minimum standards identified in Chapter [22C.200](#) MMC for day care I facilities. Parking facilities and loading areas shall be located to the rear of buildings or be constructed in a manner consistent with the surrounding residential character. Evaluation of site suitability shall be reviewed through the conditional use permit process.

(26) Public safety facilities, including police and fire, shall comply with the following:

(a) All buildings and structures shall maintain a minimum distance of 20 feet from property lines adjoining residential zones;

(b) Any buildings from which fire-fighting equipment emerges onto a street shall maintain a distance of 35 feet from such street.

(27) Accessory to an apartment development of at least 12 units, provided:

(a) The gross floor area in self-service storage shall not exceed 50 percent of the total gross floor area of the apartment dwellings on the site;

(b) All outdoor lights shall be deflected, shaded and focused away from all adjoining property;

(c) The use of the facility shall be limited to dead storage of household goods;

(d) No servicing or repair of motor vehicles, boats, trailers, lawn mowers or similar equipment;

(e) No outdoor storage or storage of flammable liquids, highly combustible or explosive materials or hazardous chemicals;

(f) No residential occupancy of the storage units;

(g) No business activity other than the rental of storage units to the apartment dwellings on the site; and

(h) A resident manager shall be required on the site and shall be responsible for maintaining the operation of the facility in conformance with the conditions of approval.

(28) All WCFs and modifications to WCFs are subject to Chapter [22C.250](#) MMC including, but not limited to, the siting hierarchy, MMC [22C.250.060](#). WCFs may be a permitted use or a conditional use subject to MMC [22C.250.040](#).

(29) Limited to commuter parking facilities for users of transit, carpools or ride-share programs, provided:

(a) They are located on existing parking lots for churches, schools, or other permitted nonresidential uses which have excess capacity available during commuting hours; and

(b) The site is adjacent to a designated arterial that has been improved to a standard acceptable to the department.

(30) Model Homes.

(a) The community development director may approve construction of model homes subject to the following conditions:

(i) No model home shall be constructed without the issuance of a building permit;

- (ii) In no event shall the total number of model homes in a preliminary subdivision be greater than nine;
- (iii) A hard-surfaced roadway to and abutting all model homes shall be constructed to standards determined by the city engineer or designee;
- (iv) Operational fire hydrant(s) must be available in accordance with the International Fire Code;
- (v) Submittal of a site plan, stamped by a registered civil engineer or licensed surveyor, delineating the location of each structure relative to existing and proposed utilities, lot lines, easements, roadways, topography and critical areas;
- (vi) Submittal of building permit applications for each of the proposed structures;
- (vii) Approval of water, sewer and storm sewer extension plans to serve the proposed structures; and
- (viii) Execution of an agreement with the city saving and holding it harmless from any damages, direct or indirect, as a result of the approval of the construction of model homes on the site.

(b) Prior to occupancy of any model home, the final plat of the subject subdivision shall be approved and recorded.

(31) Any outdoor storage areas are subject to the screening requirements of the landscape code.

(32) Subject to approval of a small farms overlay zone.

(33) May be further subject to the provisions of the Marysville shoreline master program.

(34) Only allowed in conjunction with the small farms overlay zone.

(35) Provided, that the property has received approval of a small farms overlay designation, or is larger than one acre in size.

(36) Only in conjunction with an existing or proposed school.

(37) Except racing of motorized vehicles.

(38) Level 1 and Level 2 charging only.

(39) Allowed only as an accessory use to a principal outright permitted use or permitted conditional use.

(40) The term "rapid" is used interchangeably with "Level 3" and "fast charging."

(41) Only "electric vehicle charging stations – restricted" as defined in Chapter [22A.020](#) MMC.

(42) Rapid (Level 3) charging stations are required to be placed within a parking garage.

(43) One single-family detached dwelling per existing single lot of record. Manufactured homes on single lots must meet the criteria outlined in subsection (11) of this section.

(44) Recreational vehicles (RVs) are allowed as a primary residence in an established mobile/manufactured home park (MHP) subject to the requirements of Chapter [22C.230](#) MMC, Mobile/Manufactured Home Parks.

(45) MHPs shall fulfill the requirements of Chapter [22C.230](#) MMC, Mobile/Manufactured Home Parks.

(46) Reserved.

(47) Model house sales offices are subject to the requirements of MMC [22C.110.030](#)(12).

(48) No person or entity may produce, grow, manufacture, process, accept donations for, give away, or sell marijuana concentrates, marijuana-infused products, or usable marijuana within residential zones in the city. Provided, activities in strict compliance with RCW [69.51A.210](#) and [69.51A.260](#) are not a violation of the Marysville Municipal Code.

(49) Shipping/cargo and similar storage containers are prohibited on lots within a platted subdivision and properties under one acre in size. Shipping/cargo and similar storage containers may be located on properties over one acre in size if located behind the primary residence, observe all setbacks applicable to an accessory structure, and are screened from public view.

(50) Accessory structures may not be utilized as, or converted to, a dwelling unless the structure complies with the accessory dwelling unit standards outlined in MMC [22C.180.030](#).

(51) Tiny houses or tiny houses with wheels are allowed as a primary residence in an established mobile/manufactured home park (MHP) subject to the requirements of Chapter [22C.230](#) MMC, Mobile/Manufactured Home Parks.

(52) See MMC 22C.280 for regulations for enhanced services facility.

~~(52) Enhanced services facilities are prohibited in all residential zones as such are identified and adopted in this chapter. (Ord. 3168 § 2 (Exh. A), 2020*; Ord. 3167 § 1, 2020; Ord. 3164 § 5, 2020; Ord. 3139 § 3 (Exh. B), 2019; Ord. 3054 § 8, 2017; Ord. 3022 § 8, 2016; Ord. 2959 § 6, 2014; Ord. 2898 § 8, 2012; Ord. 2852 § 10 (Exh. A), 2011).~~

~~* Code revisor's note: Ord. 3168 Section 3 states: "This interim development regulation shall be in effect for six (6) months following the effective date of this Ordinance" and shall expire June 2, 2021.~~

22C.020.060 Permitted uses. 

Specific Land Use	NB	CB	CB-WR	GC	DC	MU (63)	LI	GI	REC	P/I
Residential Land Uses										
Dwelling Units, Types:										
Townhouse					P6	P				
Multiple-family	C4	P4, C5		P4, C5	P4, P6	P				
Manufactured home	P7	P7	P7	P7	P7	P7	P7	P7		
Mobile home	P7	P7	P7	P7	P7	P7	P7	P7		
Recreational vehicle	P7	P7	P7	P7	P7	P7	P7	P7		
Tiny house or tiny house with wheels	P7	P7	P7	P7	P7	P7	P7	P7		
Senior citizen assisted	P					C				P
Caretaker's quarters (3)	P	P	P	P	P	P	P	P	P	P
Group Residences:										
Adult family home (70)	P	P	P	P	P	P				P
Convalescent, nursing, retirement	C	P			P	P				P
Residential care facility	P	P			P	P	P70	P70	P70	P
Master planned senior community (10)						C				C
Enhanced services facility (77)		<u>P</u>	<u>P</u>	<u>P</u>	<u>P</u>	<u>P</u>				
Accessory Uses:										
Home occupation (2)	P8	P8, P9	P8, P9	P8, P9	P8, P9	P8, P9	P9	P9		
Temporary Lodging:										
Hotel/motel	P	P	P	P	P	P	P75			
Bed and breakfast guesthouse (1)										
Bed and breakfast inn (1)	P	P	P	P						
Recreation/Cultural Land Uses										
Park/Recreation:										
Park	P11	P	P	P	P	P	P	P	P11	P
Marina					P			P	C	P
Dock and boathouse, private, noncommercial					P			P	P16	P
Boat launch, commercial or public					P			P		P
Boat launch, noncommercial or private					P			P	P17	P
Community center	P	P	P	P	P	P	P	P	P	P
Amusement/Entertainment:										
Theater		P	P	P	P	P				
Theater, drive-in				C						
Amusement and recreation services		P18	P18	P18	P18	P19	P	C		

Specific Land Use	NB	CB	CB-WR	GC	DC	MU (63)	LI	GI	REC	P/I
Sports club	P	P	P	P	P	P	P	P		
Golf facility (13)		P	P	P			P	P	C	
Shooting range (14)				P15			P15			
Outdoor performance center				C			C		C	C
Riding academy							P		C	
Cultural:										
Library, museum and art gallery	P	P	P	P	P	P	P	P	C	P
Church, synagogue and temple	P	P	P	P	P	P	P	P		P
Dancing, music and art center		P	P	P	P	P			C	P
General Services Land Uses										
Personal Services:										
General personal service	P	P	P	P	P	P	P	P		
Dry cleaning plant		P	P				P	P		
Dry cleaning pick-up station and retail service	P	P	P	P	P	P25	P76	P		
Funeral home/crematory		P	P	P	P	P26	P76	P		
Cemetery, columbarium or mausoleum	P24	P24	P24	P24, C20			P	P		
Day care I	P70	P70	P70	P70	P70	P70	P21, 70	P70	P70	P70
Day care II	P	P	P	P	P	P	P21			
Veterinary clinic	P	P	P	P	P	P	P76	P		
Automotive repair and service	P22	C, P28	C, P28	P			P	P		
Electric vehicle (EV) charging station (64)	P	P	P	P	P	P	P	P	P	P
EV rapid charging station (65), (66)	P	P	P	P	P67	P67	P	P		
EV battery exchange station				P			P	P		
Miscellaneous repair		P	P	P			P	P		
Social services		P	P	P	P	P				P
Kennel, commercial and exhibitor/breeding (71)		P	P	P			P	P		
Pet daycare (71), (72)		P	P	P	P	P	P76	P		
Civic, social and fraternal association		P	P	P	P	C		P		P
Club (community, country, yacht, etc.)								P		P
Health Services:										
Medical/dental clinic	P	P	P	P	P	P				P
Hospital		P	P	P	P	C				C

Specific Land Use	NB	CB	CB-WR	GC	DC	MU (63)	LI	GI	REC	P/I
Miscellaneous health	P68	P68	P68	P68	P68	P68				P68
Supervised drug consumption facility										
Education Services:										
Elementary, middle/junior high, and senior high (including public, private and parochial)		C	C	C	C	C	P	C		C
Commercial school	P	P	P		P	P27				C
School district support facility	C	P	P	P	P	P	P	P		P
Vocational school		P	P	P	P	P27				P
Government/Business Service Land Uses										
Government Services:										
Public agency office	P	P	P	P	P	P	P	P		P
Public utility yard				P			P			P
Public safety facilities, including police and fire	P29	P	P	P	P	P	P			P
Utility facility	P	P	P	P		C	P	P		P
Private storm water management facility	P	P	P	P	P	P	P	P		P
Public storm water management facility	P	P	P	P	P	P	P	P		P
Business Services:										
Contractors' office and storage yard				P30	P30	P30	P	P		
Interim recycling facility		P23	P23	P23			P			P
Taxi stands		P	P	P			P	P		
Trucking and courier service		P31	P31	P31			P	P		
Warehousing and wholesale trade				P			P	P		
Mini-storage (36)							P76	P		
Freight and cargo service				P			P	P		
Cold storage warehousing							P	P		
General business service and office	P	P	P	P	P	P30	P	P		
Commercial vehicle storage							P	P		
Professional office	P	P	P	P	P	P	P			
Miscellaneous equipment rental		P30, 37	P30, 37	C38		P30, 37	P	P		
Automotive rental and leasing				P			P	P		
Automotive parking	P	P	P	P	P	P	P	P		
Research, development and testing				P			P	P		
Heavy equipment and truck repair							P	P		
Automobile holding yard				C			P	P		

Specific Land Use	NB	CB	CB-WR	GC	DC	MU (63)	LI	GI	REC	P/I
Commercial/industrial accessory uses (73)	P39, 40	P39	P39	P39	P39, 40	P39, 40	P	P		
Adult facility								P33		
Factory-built commercial building (35)	P	P	P	P	P		P	P		
Wireless communication facility (32)	P, C	P, C	P, C	P, C	P, C	P, C	P, C	P, C		P, C
State-Licensed Marijuana Facilities:										
Marijuana cooperative (69)										
Marijuana processing facility – Indoor only (69)										
Marijuana production facility – Indoor only (69)										
Marijuana retail facility (69)										
Retail/Wholesale Land Uses										
Building, hardware and garden materials	P47	P	P	P	P	P47	P76	P		
Forest products sales		P	P	P			P			
Department and variety stores	P	P	P	P	P	P	P76			
Food stores	P	P	P	P	P	P45	P76			
Agricultural crop sales		P	P	P		C	P76			
Storage/retail sales, livestock feed							P76	P		
Motor vehicle and boat dealers		P	P	P			P	P		
Motorcycle dealers		C	C	P	P49		P	P		
Gasoline service stations	P	P	P	P	P		P76	P		
Eating and drinking places	P41	P	P	P	P	P46	P46	P		
Drug stores	P	P	P	P	P	P	P76	P		
Liquor stores		P	P	P						
Used goods: antiques/secondhand shops		P	P	P	P	P				
Sporting goods and related stores		P	P	P	P	P				
Book, stationery, video and art supply stores	P	P	P	P	P	P				
Jewelry stores		P	P	P	P	P				
Hobby, toy, game shops	P	P	P	P	P	P				
Photographic and electronic shops	P	P	P	P	P	P				
Fabric and craft shops	P	P	P	P	P	P				
Fuel dealers				P43			P43	P43		
Florist shops	P	P	P	P	P	P				
Pet shops	P	P	P	P	P	P				
Tire stores		P	P	P	P		P76	P		

Specific Land Use	NB	CB	CB-WR	GC	DC	MU (63)	LI	GI	REC	P/I
Bulk retail		P	P	P			P76			
Auction houses				P42			P76			
Truck and heavy equipment dealers							P	P		
Mobile home and RV dealers				C			P	P		
Retail stores similar to those otherwise named on this list	P	P	P	P	P	P48	P44, 76	P44		
Automobile wrecking yards							C	P		
Manufacturing Land Uses										
Food and kindred products		P50, 52	P50, 52	P50			P50	P		
Winery/brewery		P53	P53	P	P53	P53	P	P		
Textile mill products							P	P		
Apparel and other textile products				C			P	P		
Wood products, except furniture				P			P	P		
Furniture and fixtures				P			P	P		
Paper and allied products							P	P		
Printing and publishing	P51	P51	P51	P		P51	P	P		
Chemicals and allied products							C	C		
Petroleum refining and related industries							C	C		
Rubber and misc. plastics products							P	P		
Leather and leather goods							C	C		
Stone, clay, glass and concrete products							P	P		
Primary metal industries							C	P		
Fabricated metal products				C			P	P		
Industrial and commercial machinery							C	P		
Heavy machinery and equipment							C	P		
Computer and office equipment				C			P			
Electronic and other electric equipment				C			P			
Railroad equipment							C	P		
Miscellaneous light manufacturing				P54, 74	P54		P	P		
Motor vehicle and bicycle manufacturing							C	P		
Aircraft, ship and boat building							C	P		
Tire retreading							C	P		
Movie production/distribution				P			P			
Resource Land Uses										

Specific Land Use	NB	CB	CB-WR	GC	DC	MU (63)	LI	GI	REC	P/I
Agriculture:										
Growing and harvesting crops							P	P	P	
Raising livestock and small animals							P	P	P	
Greenhouse or nursery, wholesale and retail				P			P	P	C	
Farm product processing							P	P		
Forestry:										
Growing and harvesting forest products							P			
Forest research							P			
Wood waste recycling and storage							C	C		
Fish and Wildlife Management:										
Hatchery/fish preserve (55)							P	P	C	
Aquaculture (55)							P	P	C	
Wildlife shelters	C	C	C						P	
Mineral:										
Processing of minerals							P	P		
Asphalt paving mixtures and block							P	P		
Regional Land Uses										
Jail		C	C	C			C			
Regional storm water management facility		C	C	C	C		C	C		P
Public agency animal control facility				C			P	P		C
Public agency training facility		C56	C56	C56		C56	C57			C57
Nonhydroelectric generation facility	C	C	C	C			C	C		C
Energy resource recovery facility							C			
Soil recycling/incineration facility							C	C		
Solid waste recycling								C		C
Transfer station							C	C		C
Wastewater treatment facility							C	C		C
Transit bus base				C			P			C
Transit park and pool lot	P	P	P	P	P	P	P	P		P
Transit park and ride lot	P	P	P	P	P	P	P	P		C
School bus base	C	C	C	C			P			C58
Racetrack	C59	C59	C59	C			P			
Fairground							P	P		C
Zoo/wildlife exhibit		C	C	C						C
Stadium/arena				C			C	P		C

Specific Land Use	NB	CB	CB-WR	GC	DC	MU (63)	LI	GI	REC	P/I
College/university	C	P	P	P	P	P	P	P		C
Secure community transition facility								C60		
Opiate substitution treatment program facilities		P61, 62	P61, 62	P61, 62	P61, 62		P62	P62		

(Ord. 3168 § 2 (Exh. A), 2020**; Ord. 3164 § 6, 2020; Ord. 3159 § 3, 2020; Ord. 3137 § 3 (Exh. B), 2019; Ord. 3086 § 1, 2018; Ord. 3085 § 3, 2018; Ord. 3071 § 4, 2017; Ord. 3057 § 6, 2017*; Ord. 3054 § 12, 2017; Ord. 3022 § 9, 2016; Ord. 2985 § 5, 2015; Ord. 2981 § 1, 2015; Ord. 2980 § 1, 2015; Ord. 2959 § 7, 2014; Ord. 2932 § 3, 2013; Ord. 2898 § 9, 2012; Ord. 2852 § 10 (Exh. A), 2011).

* Code reviser’s note: Ord. 3057 amends this section without taking into account the amendments of Ord. 3054. The amendments of Ord. 3054 have been retained per the intent of the city.

~~** Code reviser’s note: Ord. 3168 Section 3 states: “This interim development regulation shall be in effect for six (6) months following the effective date of this Ordinance” and shall expire June 2, 2021.~~

22C.020.070 Permitted uses – Development conditions.

(1) Bed and breakfast guesthouses and inns are subject to the requirements and standards contained in Chapter [22C.210](#) MMC, Bed and Breakfasts.

(2) Home occupations are subject to the requirements and standards contained in Chapter [22C.190](#) MMC, Home Occupations.

(3) Limited to one dwelling unit for the purposes of providing on-site service and security of a commercial or industrial business. Caretaker’s quarters are subject to the provisions set forth in Chapter [22C.110](#) MMC, entitled “Temporary Uses.”

(4) All units must be located above a street-level commercial use.

(5) Twenty percent of the units, but no more than two total units, may be located on the street level of a commercial use, if conditional use permit approval is obtained and the units are designed exclusively for ADA accessibility. The street-level units shall be designed so that the units are not located on the street front and primary access is towards the rear of the building.

(6) Permitted on the ground floor in the southwest sector of downtown vision plan area, as incorporated into the city of Marysville comprehensive plan.

(7) Manufactured homes, mobile homes, recreational vehicles, and tiny houses with wheels are only allowed in existing mobile/manufactured home parks.

- (8) Home occupations are limited to home office uses in multifamily dwellings. No signage is permitted in townhouse or multifamily dwellings.
- (9) Permitted in a legal nonconforming or conforming residential structure.
- (10) Subject to Chapter [22C.220](#) MMC, Master Planned Senior Communities.
- (11) The following conditions and limitations shall apply, where appropriate:
- (a) Parks are permitted in residential and mixed use zones when reviewed as part of a subdivision or multiple-family development proposal; otherwise, a conditional use permit is required;
 - (b) Lighting for structures and fields shall be directed away from residential areas; and
 - (c) Structures or service yards shall maintain a minimum distance of 50 feet from property lines adjoining residential zones.
- (12) Recreational vehicle parks are subject to the requirements and conditions of Chapter [22C.240](#) MMC.
- (13) Golf Facility.
- (a) Structures, driving ranges and lighted areas shall maintain a minimum distance of 50 feet from property lines adjoining residential zones.
 - (b) Restaurants are permitted as an accessory use to a golf course.
- (14) Shooting Range.
- (a) Structures and ranges shall maintain a minimum distance of 50 feet from property lines adjoining residential zones;
 - (b) Ranges shall be designed to prevent stray or ricocheting projectiles or pellets from leaving the property; and
 - (c) Site plans shall include safety features of the range; provisions for reducing noise produced on the firing line; and elevations of the range showing target area, backdrops or butts.
- (15) Only in an enclosed building.
- (16) Dock and Boathouse, Private, Noncommercial.
- (a) The height of any covered over-water structure shall not exceed 20 feet as measured from the line of ordinary high water;
 - (b) The total roof area of covered, over-water structures shall not exceed 1,000 square feet;

(c) The entirety of such structures shall have not greater than 50 percent of the width of the lot at the natural shoreline upon which it is located;

(d) No over-water structure shall extend beyond the average length of all pre-existing over-water structures along the same shoreline and within 300 feet of the parcel on which proposed. Where no such pre-existing structures exist within 300 feet, the pier length shall not exceed 50 feet;

(e) Structures permitted hereunder shall not be used as a dwelling; and

(f) Covered structures are subject to a minimum setback of five feet from any side lot line or extension thereof. No setback from adjacent properties is required for any uncovered structure, and no setback from water is required for any structure permitted hereunder.

(17) Boat Launch, Noncommercial or Private.

(a) The city may regulate, among other factors, required launching depth, and length of docks and piers;

(b) Safety buoys shall be installed and maintained separating boating activities from other water-oriented recreation and uses where this is reasonably required for public safety, welfare and health; and

(c) All site improvements for boat launch facilities shall comply with all other requirements of the zone in which it is located.

(18) Excluding racetrack operation.

(19) Amusement and recreation services shall be a permitted use if they are located within an enclosed building, or a conditional use if located outside. In both instances they would be subject to the exclusion of a racetrack operation similar to other commercial zones.

(20) Structures shall maintain a minimum distance of 100 feet from property lines adjoining residential zones.

(21) Permitted as an accessory use; see MMC [22A.020.020](#), the definition of "Accessory use, commercial/industrial."

(22) Only as an accessory to a gasoline service station; see retail and wholesale permitted use table in MMC [22C.020.060](#).

(23) All processing and storage of material shall be within enclosed buildings and excluding yard waste processing.

(24) Limited to columbariums accessory to a church; provided, that existing required landscaping and parking are not reduced.

(25) Drive-through service windows in excess of one lane are prohibited in Planning Area 1.

(26) Limited to columbariums accessory to a church; provided, that existing required landscaping and parking are not reduced.

(27) All instruction must be within an enclosed structure.

(28) Car washes shall be permitted as an accessory use to a gasoline service station.

(29) Public Safety Facilities, Including Police and Fire.

(a) All buildings and structures shall maintain a minimum distance of 20 feet from property lines adjoining residential zones;

(b) Any buildings from which fire-fighting equipment emerges onto a street shall maintain a distance of 35 feet from such street.

(30) Outdoor storage of materials or vehicles must be accessory to the primary building area and located to the rear of buildings. Outdoor storage is subject to an approved landscape plan that provides for effective screening of storage, so that it is not visible from public right-of-way or neighboring properties.

(31) Limited to self-service household moving truck or trailer rental accessory to a gasoline service station.

(32) All WCFs and modifications to WCFs are subject to Chapter [22C.250](#) MMC including but not limited to the siting hierarchy, MMC [22C.250.060](#). WCFs may be a permitted use or a CUP may be required subject to MMC [22C.250.040](#).

(33) Subject to the conditions and requirements listed in Chapter [22C.030](#) MMC.

(34) Reserved.

(35) A factory-built commercial building may be used for commercial purposes subject to the following requirements:

(a) A factory-built commercial building must be inspected at least two times at the factory by the State Building and Electrical Inspector during the construction process, and must receive a state approval stamp certifying that it meets all requirements of the International Building and Electrical Codes. At the building site, the city building official will conduct foundation, plumbing and final inspections; and

(b) A factory-built commercial building cannot be attached to a metal frame allowing it to be mobile. All structures must be placed on a permanent, poured-in-place foundation. The foundation shall be structurally engineered to meet the requirements set forth in Chapter 16 of the International Building Code.

(36) Mini-storage facilities are subject to the development standards outlined in Chapter [22C.170](#) MMC.

(37) Except heavy equipment.

- (38) With outdoor storage and heavy equipment.
- (39) Incidental assembly shall be permitted; provided, it is limited to less than 20 percent of the square footage of the site excluding parking.
- (40) Light industrial uses may be permitted; provided, there is no outdoor storage of materials, products or vehicles.
- (41) Excluding drinking places such as taverns and bars and adult entertainment facilities.
- (42) Excluding vehicle and livestock auctions.
- (43) If the total storage capacity exceeds 6,000 gallons, a conditional use permit is required.
- (44) The retail sale of products manufactured on site shall be permitted; provided, that not more than 20 percent of the constructed floor area in any such development may be devoted to such retail use.
- (45) Limited to 5,000 square feet or less.
- (46) Eating and Drinking Places.
 - (a) Limited to 4,000 square feet or less.
 - (b) Drive-through service windows in excess of one lane are prohibited in Planning Area 1.
 - (c) Taverns, bars, lounges, etc., are required to obtain a conditional use permit in the mixed use zone.
- (47) Limited to hardware and garden supply stores.
- (48) Limited to convenience retail, such as video, and personal and household items.
- (49) Provided there is no outdoor storage and/or display of any materials, products or vehicles.
- (50) Except slaughterhouses.
- (51) Limited to photocopying and printing services offered to the general public.
- (52) Limited to less than 10 employees.
- (53) In conjunction with an eating and drinking establishment.
- (54) Provided there is no outdoor storage and/or display of any materials, products or vehicles.
- (55) May be further subject to the provisions of city of Marysville shoreline management program.
- (56) Except weapons armories and outdoor shooting ranges.

(57) Except outdoor shooting ranges.

(58) Only in conjunction with an existing or proposed school.

(59) Except racing of motorized vehicles.

(60) Limited to land located along east side of 47th Avenue NE alignment, in the east half of the northeast quarter of Section 33, Township 30N, Range 5E, W.M., and in the northeast quarter of the southeast quarter of Section 33, Township 30N, Range 5E, W.M., and land located east side of SR 529, north of Steamboat Slough, south and west of Ebey Slough (a.k.a. TP No. 300533-002-004-00) and in the northwest and southwest quarters of Section 33, Township 30N, Range 5E, W.M., as identified in Exhibit A, attached to Ordinance No. 2452.

(61) Opiate substitution treatment program facilities permitted within commercial zones are subject to Chapter [22G.070](#) MMC, Siting Process for Essential Public Facilities.

(62) Opiate substitution treatment program facilities, as defined in MMC [22A.020.160](#), are subject to the standards set forth below:

(a) Shall not be established within 300 feet of an existing school, public playground, public park, residential housing area, child-care facility, or actual place of regular worship established prior to the proposed treatment facility.

(b) Hours of operation shall be restricted to no earlier than 6:00 a.m. and no later than 7:00 p.m. daily.

(c) The owners and operators of the facility shall be required to take positive ongoing measures to preclude loitering in the vicinity of the facility.

(63) Permitted uses include Whiskey Ridge zones.

(64) Level 1 and Level 2 charging only.

(65) The term “rapid” is used interchangeably with Level 3 and fast charging.

(66) Rapid (Level 3) charging stations are required to comply with the design and landscaping standards outlined in MMC [22C.020.265](#).

(67) Rapid (Level 3) charging stations are required to be placed within a parking garage.

(68) Excepting “marijuana (cannabis) dispensaries,” “marijuana (cannabis) collective gardens,” and “marijuana cooperatives” as those terms are defined or described in this code and/or under state law; such facilities and/or uses are prohibited in all zoning districts of the city of Marysville.

(69) No person or entity may produce, grow, manufacture, process, accept donations for, give away, or sell marijuana concentrates, marijuana-infused products, or usable marijuana within commercial, industrial, recreation, and public institution zones in the city. Provided, activities in strict compliance with RCW [69.51A.210](#) and [69.51A.260](#) are not a violation of the Marysville Municipal Code.

(70) Permitted within existing legal nonconforming single-family residences.

(71) Subject to the requirements set forth in MMC 10.04.460.*

(72) Pet daycares are restricted to indoor facilities with limited, supervised access to an outdoor fenced yard. Overnight boarding may be permitted as a limited, incidental use. Both outdoor access and overnight boarding privileges may be revoked or modified if the facility is not able to comply with the noise standards set forth in WAC [173-60-040](#).*

(73) Shipping/cargo and similar storage containers may be installed on commercial or industrial properties provided they are screened from public view pursuant to MMC [22C.120.160](#), Screening and impact abatement.

(74) Tanks, generators, and other machinery which does not generate nuisance noise may be located in the service/loading area. Truck service/loading areas shall not face the public street and shall be screened from the public street.

(75) Hotels/motels are prohibited within Arlington Airport Inner Safety Zones (ISZ) 2, 3, and 4. Hotel/motels that are proposed to locate within Arlington Airport Protection Subdistricts B and C shall be required to coordinate with the Arlington Municipal Airport to ensure that height, glare, and other aspects of the hotels/motels are compatible with air traffic and airport operations.

(76) Use limited to properties that have property frontage along State Avenue/Smokey Point Boulevard.

[\(77\) See MMC 22C.280 for regulations for enhanced services facility.](#)

~~(77) Enhanced services facilities are prohibited in all commercial and industrial zones as such are identified and adopted in this chapter. (Ord. 3168 § 2 (Exh. A), 2020**; Ord. 3164 § 7, 2020; Ord. 3159 § 4, 2020; Ord. 3137 § 3 (Exh. B), 2019; Ord. 3086 § 2, 2018; Ord. 3054 § 13, 2017; Ord. 3022 § 10, 2016; Ord. 2985 § 6, 2015; Ord. 2981 § 2, 2015; Ord. 2979 § 4, 2014; Ord. 2959 § 8, 2014; Ord. 2932 § 4, 2013; Ord. 2898 § 10, 2012; Ord. 2852 § 10 (Exh. A), 2011).~~

*Code reviser's note: Ord. 2985 added these subsections as (70) and (71). They have been renumbered as (71) and (72) to avoid duplicating the subsection added by Ord. 2981.

~~** Code reviser's note: Ord. 3168 Section 3 states: "This interim development regulation shall be in effect for six (6) months following the effective date of this Ordinance" and shall expire June 2, 2021.~~

EXHIBIT B
Chapter 22C.280
Regulations for Enhanced Services Facility.

22C.280.010 Purpose. The purpose of this section is to:

1. provide for a needed community service while ensuring that adequate public facilities are available to the residents of enhanced services facilities; and
2. promote compatibility with surrounding land uses.

22C.280.020. Applicability. The standards in this section apply to any “enhanced services facility”, as defined in Chapter 22A.020 MMC.

22C.280.030. Notice Requirements. At least fifteen (15) days prior to filing an application with the City to establish an enhanced services facility, the owner and/or sponsor shall mail written notice to owners of contiguous properties and to the Community Development Department of their intention to establish the facility. The notice shall list the name and contact information for the owner or sponsor, to provide neighboring property owners the opportunity to contact them with questions, and include a description of the proposed facility and proposed number of residents. The owner or sponsor shall address questions or concerns from neighboring property owners to the extent possible in the management plan required by MMC 22C.280.040.

22C.280.040. Management Plan Required. The owner or sponsor of the facility shall provide the Community Development Director with a management plan for the facility addressing the following:

1. how the facility can appropriately meet the assessed needs of potential residents through appropriate staffing and best management practices;
2. potential impacts on nearby residential uses and proposed methods to mitigate those impacts;
3. facility management, including 24-hour contact information for persons responsible to resolve concerns pertaining to the facility, and procedures for updating neighbors with changes in contact information;
4. staffing, supervision and security arrangements appropriate to the facility; and
5. a communications plan for providing information to the surrounding neighborhood.

22C.280.050. Other Requirements.

1. The facility shall obtain all necessary certificates and approvals from state and federal agencies.
2. The facility shall serve only individuals who do not pose a direct threat and a significant risk to others, and who have been assessed as medically and psychiatrically stable.
3. No more than one enhanced services facility shall be permitted per site.
4. In the R-18 and R-28 zones, an enhanced services facility shall be located either within one-quarter mile of a public transit route, or within one-quarter mile of property located in the DC, NB, MU, CB, CB-WR or GC zones.