

Addendum to:

Geotechnical Recommendations

Harbor View Short Plat

5130 61st Street NE

Marysville, Washington

May 2, 2023

CMT Job No. 18639

Infiltration/Drainage Recommendations

The initial infiltration test for the above project was performed 11-May-2022. In response to comments by Marysville staff, a second infiltration test was performed at the site on 29-Apr-2024 (within the “wet season”) near the initial test but closer to the east lot line. The results of this second test indicated an infiltration rate of approximately 1.5 minutes per inch (40 inches per hour). This rate is significantly greater than the results of the initial test [approximately 3.5 minutes per inch (17 inches per hour)]. This means that the results of the initial test, though performed just outside the “wet season” window, is indicative of expected infiltration rates within the wet season. It is recommended that the results of the initial test be used for design purposes.

Evan G Nixon, P.E. (UT)

Nixon E&D, LLC